 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	1 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

PURPOSE/OBJECTIVE:

This document provides National Grid personnel, consultants and contractors with Best Management Practices (BMPs) for conducting work on electric and natural gas transmission and distribution rights-of-ways (ROWs) and substations in New England.

WHO:

These BMPs are to be followed by all personnel conducting work on Company electric and gas ROWs and substations in New England. These BMPs do not apply to Company employees and contractors performing routine vegetation management activities that are not a part of construction or re-construction projects. Employees and contractors maintaining vegetation on Company ROWs and substations must follow the National Grid ROW Vegetation and Substation Vegetation Management Plans.

DEFINITIONS:

Refer to **Glossary** in **Appendix 1** and **Acronyms** in **Appendix 2**.

WHAT TO DO:

1.0 Project Planning

Prior to the start of any project (proposed new facilities or maintenance of existing facilities), the Project Engineer or other project planner shall determine whether any environmental permits or approvals are required, per the state-specific EG-301 environmental checklists. Any questions regarding which activities may be conducted in regulated areas or within environmentally sensitive areas shall be referred to the National Grid Environmental Scientist or Project Environmental Consultant.

All new construction and maintenance projects shall follow clear and enforceable environmental performance standards, which is the purpose for which these BMPs have been compiled.


1.1 Avoidance and Minimization

Measures shall always be taken to avoid impacts to wetlands, waterways, rare species habitats, known below and above ground historical/archeological resources and other environmentally sensitive areas. If avoidance is not possible, then measures shall be taken to minimize the extent of impacts. Alternate access routes or staging areas shall always be considered. Below is a list of methods that shall be considered where impacts are unavoidable:

- Use existing ROW access where available. Keep to approved routes and roads without deviating from them or making them wider.
- Off-ROW access shall never be assumed and shall be coordinated through National Grid Real Estate before being implemented.
- Where no existing ROW access is present, avoid wetlands and if a wetland crossing is necessary, cross wetlands at the most narrow point possible or at the location of a previously used crossing (if evident). Figure 1 below illustrates this minimization technique.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	2 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	


- Avoid and minimize stream crossings.
- Minimize the width of typical access roads through wetlands to a maximum width of 16 feet.
- Conduct work manually (without using motorized equipment) in wetlands, wherever possible.
- Use construction mats in wetlands to minimize soil disturbance and rutting when crossing or working within wetlands. When not using mats for access, standard vehicles shall not be allowed to drive across wetlands without the prior approval of the National Grid Environmental Scientist. Use of a low ground pressure (LGP) vehicle may be a feasible alternative to mats provided that such LGP vehicle use has been reviewed and approved by the National Grid Environmental Scientist. See Section 7.0.
- Coordinate the timing of work to cause the least impacts during the regulatory low-flow period under normal conditions, when water/ground is frozen, after the spring songbird nesting season, and, outside of the anticipated amphibian migration window (mid-February to mid-June). Refer to the United States Army Corps of Engineers (USACE) state-specific General Permit for the definition of the low-flow period in each state at: <http://www.nae.usace.army.mil/Missions/Regulatory/State-General-Permits/>. A summary table is provided in Section 7.0.
- Seek alternative routes or work methods to minimize impact.

**National Grid
Environmental Guidance**

Doc No.:	EG-303NE
Rev. No.:	15
Page No.:	3 of 50
Date:	08/06/2020


SUBJECT
ROW Access, Maintenance and Construction Best
Management Practices for New England

REFERENCE
EP-3; Natural Resource Protection



Appi

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	4 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

1.2 Historically Significant Areas

Areas that have been identified as historically and/or culturally significant shall be avoided in accordance with site-specific avoidance plans, as applicable. Refer to the project-specific Environmental Field Issue (EFI) for any applicable avoidance plans or consult with the National Grid Environmental Scientist. Demarcation of these areas to be avoided shall use staked orange snow fencing or an equivalent physical barrier (not just ribbon flagging) and signage. Refer to Section 14.0 for signage guidance.

1.3 Rare Species Habitat

Work within areas that have been identified as mapped rare species habitat shall follow site-specific requirements, as applicable. In Massachusetts, maintenance activities within mapped habitat (known as Priority Habitat of Rare Species) shall follow the BMPs outlined in the Natural Heritage Endangered Species Program (NHESP)-approved National Grid Operation and Maintenance Plan. Work in mapped rare species habitat may require, at a minimum, turtle training for crews and sweeps of work areas for turtles, botanist identification of rare plant locations and avoidance of these locations, and protection of vernal pools, all prior to the start of work. Demarcation of these areas to be avoided (e.g., rare plant populations, overwintering turtles, nests) shall use staked orange snow fencing or an equivalent physical barrier (not just ribbon flagging) and signage. Refer to Section 14.0 for signage guidance.

Where new substations are being constructed or existing substations are undergoing a rebuild or expansion, and the substations are located in mapped rare turtle habitat, project team members should consider fenceline improvements or measures needed to prevent/eliminate turtle entrance into the substation or allow multiple points for easy egress such that turtles are not trapped within the substation fenceline.

Other requirements may apply in NH, VT and RI. Refer to the project-specific EFI for any applicable measures or consult with the National Grid Environmental Scientist.

1.4 Meetings


Pre-permitting meetings shall take place early in the project development process to determine what permits are triggered by the proposed work and the timeline required for permitting. During these meetings, the team shall develop access plans and BMPs to be used during construction of the project.

Field / Constructability review meetings shall take place on-site to evaluate construction site access and job site set-up, to ensure that the project can proceed as permitted. It is at this point in time where work areas, pulling locations, laydown areas, parking areas, and equipment storage areas are evaluated and located. Off-ROW areas under consideration should be included in this discussion.

Prior to submitting permit plans to regulatory authorities, the construction group (contractor or National Grid) shall review the plans for final sign off.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	5 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Pre-construction meetings are typically held prior to the commencement of all work to appoint responsible parties, discuss timing of work, and further consider options to avoid and/or minimize impacts to sensitive areas. These meetings can occur on- or off-site and shall include all the willing and available stakeholders (i.e., utility employees, contractors, consultants, inspectors, and/or monitors, and regulatory personnel). Training of crews and supervisors of the EFI, Stormwater Pollution Prevention Plan (SWPPP), rare species, and other permit requirements shall be conducted at a pre-construction meeting.

Pre-job briefings shall be conducted daily or otherwise routinely scheduled meetings shall be conducted on-site with the work crew throughout the duration of the work. These meetings are a way of keeping everyone up to date, confirming there is consensus on work methods and responsibilities, and ensuring that tasks are being fulfilled with as little impact to the environment as possible.

The Project Environmental Scientist/Monitor and Construction Project Manager shall communicate regularly (e.g. weekly or bi-weekly meetings or phone conversations) to discuss the work completed since last communication (i.e. work locations, wetland impacts, equipment used, and unexpected delays or work conditions). These meetings or calls shall include the expected schedule of construction for the upcoming week, the long term construction plans, and planned methods for working near/in wetlands. Both the Project Environmental Scientist/Monitor and Construction Project Manager shall work together so the Project complies with all environmental permits and regulations. When changes to the Project scope or agreed work plan are proposed they shall be done so with the final approval of the National Grid Environmental Scientist.

1.5 Communication of Project Specific Environmental Requirements


Project specific environmental concerns, to include sensitive resources, permits, approved access and time-of-year or other restrictions, shall be communicated to the project team and be included as part of the Pre-Bid and Pre-Construction Meetings. Project specific requirements shall be communicated to the project manager/construction manager/engineering group using the following guidelines:

Environmental Field Issue – The EFI will be a full document consisting of narrative, project permits, access and matting plans. A table summarizing pertinent (but not all) permit conditions and the responsible party for those conditions shall be included in the EFI. Copies of all permits should be included as attachments. This will be prepared for most projects with multiple permits or large, complex projects (siting board, Section 404, 401 WQC, SWPPP). There shall be EFI training at the pre-construction meeting. The National Grid EFI template is located in **EI-303NE**.

Simplified Environmental Field Issue – The Simplified EFI is a memorandum containing environmental resources present, project permit(s), access and matting plans and a table summarizing relevant permit conditions and responsible party for those conditions. Copies of all permits should be included as attachments. The Simplified EFI will be prepared for most projects with 1 or 2 permits (Order of Conditions, S404 Cat 1). The Simplified EFI should also be provided for projects that have environmental resources present, but the scope of the project does not trigger environmental permitting (e.g., the scope of work qualifies for maintenance exemption(s)). The resources present

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	6 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

shall be discussed at the Pre-Bid and Pre-Construction meetings and any changes in scope will require additional review by the National Grid project team.

E-mail delivery of Permit and any Sediment/Erosion control or BMP plan – For those projects with only one permit (eg., MA Order of Conditions, RI DEM permit, RI CRMC permit, NH Utility Notification) or projects with a sediment & erosion control plan (local town requirement or for exempt maintenance work), a copy of the permit and any applicable plan will be emailed to the Project Manager (and the project team where deemed necessary) to be incorporated into the Construction Field Issue.

STORMS work management system input – For STORMS work, no EFI is prepared unless multiple permits are required for the project (see guidance above). If only a MA Order of Conditions, MA Determination of Applicability, RI DEM permit, RI CRMC permit, RI SESC Approval, or NH Utility Notification is required, then the permit is attached in the Documents tab and conditions noted in Remarks/Comments section. Standard STORMS boilerplate language is located in **EI-303NE**.

1.6 Timing of Work

Regulatory authorities may place seasonal or time-of-year restrictions on project construction elements. These time-of-year restrictions may be state or permit-specific, and shall be adhered to.

Work during frozen conditions. Activities conducted once wetland areas are frozen sufficient to minimize rutting and other impacts to the surrounding environment may be authorized by the National Grid Environmental Scientist. Work during this time also generally reduces disturbance of aquatic and terrestrial wildlife movement by avoiding sensitive breeding and nesting seasons. When not using mats for access, vehicles shall not be allowed to drive across wetlands without the prior approval of the National Grid Environmental Scientist.

Work during the regulatory low-flow period. Conducting work during the low-flow period can reduce impacts to surface water and generally avoids spawning and breeding seasons of aquatic organisms. If the water is above normal seasonal levels, adjustments to work activities and methods are required.

1.7 Alternate Access

1.7.1 Manual Access


In some cases such as for smaller projects, work areas can be accessed manually. This includes access on foot through upland and shallow wetland areas, access by boat through open water or ponded areas, and climbing of structures where possible. Smaller projects, such as repair of individual structures, or parts of structures, that do not categorically require the use of heavy machinery, shall be accessed manually to the greatest extent practicable.

1.7.2 Use of Overhead/Aerial Access

Using helicopters can be expensive and is not always feasible, but it may be appropriate in some situations in order to get workers and equipment to a site that otherwise may be very difficult to access. The use of overhead and/or aerial equipment may be beneficial for work in areas where larger water bodies, deep crevices, or mountainous areas hinder ground access. The landing area for

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	7 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

helicopters shall be reviewed for environmentally sensitive resources. Use of helicopters requires Project Manager and Senior Management approval.

2.0 Inspection, Monitoring and Maintenance

All construction practices and controls shall be inspected on a regular basis and in accordance with all applicable permits and local, state, and federal regulations to avoid and correct ANY damage to sensitive areas.

The construction crews shall be responsible for completing daily inspections, and IMMEDIATELY bring any **damage or observed erosion, or failed erosion controls** to the attention of the Person-In-Charge and the National Grid Environmental Scientist. Where applicable and/or as directed by environmental permits issued for the project, the Project Environmental Consultant shall conduct weekly (at a minimum) inspections of the project work areas and shall document their inspection using the Stormwater, Wetlands & Priority Habitat Environmental Compliance Site Inspection / Monitoring Report form found in **Appendix 3** and issue the report within 24 hours. The Person-in-Charge shall work with the National Grid Environmental Scientist and the Project Environmental Consultant to determine when and how the repairs shall be made.

Project-specific Action Logs and Long-Term Restoration Logs are prepared as needed by the National Grid Environmental Scientist or the Project Environmental Consultant to track issues and/or repairs and assign responsible parties.

3.0 Best Management Practices

The BMP sections presented in this EG address access, construction, snow and ice management, structures in wetlands, access road maintenance and repair, clean-up and restoration standards, ROW gates, field refueling and maintenance operations, management of spills/releases, and a summary of key construction BMPs.

Note that BMPs shown on any permit drawings for a specific project may need to be revised and or supplemented during the execution of a project based on unforeseen or unexpected factors such as extreme weather or unknown subsurface conditions. It is the responsibility of the Contractor to work with the National Grid Environmental Scientist and/or the Project Environmental Consultant to identify necessary changes and to ensure that construction-related impacts to wetlands, water bodies and other environmentally sensitive areas are avoided.


Any deviation from the approved BMPs shown in the EFI and/or SWPPP plans shall be communicated immediately to the National Grid Environmental Scientist as it may require additional permitting or could result in a permit violation.

3.1 Wetland Boundary Demarcation

Prior to the start of any activity conducted under an environmental permit, wetland boundaries shall be reviewed. Flagging for wetland boundaries, stream banks and other resource areas shall be

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	8 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

refreshed as needed. This may become particularly important when the original flagging was placed in previous seasons and now may have become obscured.

3.2 Sedimentation and Erosion Controls

Appropriate sedimentation and erosion control devices shall be installed at work sites, in accordance with permit conditions and/or regulatory approvals, and as needed to prevent adverse impacts to water resources and adjacent properties.

The overall purpose of such controls is to prevent and control the movement of disturbed soil and sediment from work sites to adjacent, undisturbed areas, and particularly to water resources, public roads and adjacent properties. All proprietary controls shall be installed per manufacturer's recommendations and specifications.

Appropriate sedimentation and erosion control devices include but are not limited to: silt fencing, straw bales, wood chip bags, straw wattles, compost socks, erosion control blankets, mulch, slope interruption practices, flocculent powder/blocks and storm drain/catch basin inlet protection. Such controls shall be installed between the work area and environmentally sensitive areas such as wetlands, streams, drainage courses, roads and adjacent property when work activities shall disturb soils and result in a potential for causing sedimentation and erosion.

In Massachusetts, use of monofilament-encased wattles shall be avoided in mapped Priority Habitat for snakes and amphibians. For projects with work within mapped Priority Habitat for snakes and amphibians, wattles that are encased in a sock, hemp, fiber, or movable jute netting are required to prevent entrapment. Also, "wildlife gaps" should occur every 50 feet, if possible, given wetland permit conditions. This spacing of the wattles allows snakes and amphibians to move across the ROW. Refer to the Amphibian and Reptile BMPs in **Appendix 4**.

Staked straw bales often serve as the demarcation of the limits of work and/or sensitive areas to be avoided. Work shall never be conducted outside the limit of erosion controls without prior approval from the National Grid Environmental Scientist.


Project plans depict proposed erosion controls, however field conditions may warrant additional practices be implemented (e.g., wet conditions, frozen conditions, poorly drained soils, steep slopes, materials used for work pads, transition areas to construction mats, number of trips across work areas, etc.).

Any deviation from the approved erosion controls shown in the EFI and/or SWPPP plans needs to be communicated immediately to the National Grid Environmental Scientist as it may require additional permitting or result in a permit violation.

Appendix 4 provides typical sketches of common sedimentation and erosion controls. If a SWPPP is required for the project, maintenance and inspection of erosion controls shall follow the SWPPP requirements. Sedimentation and erosion controls shall be properly maintained and inspected on a

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	9 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

periodic basis, until work sites are properly stabilized and restored. Inspections shall be documented using the Inspection Form “Storm Water, Wetlands & Priority Habitat Environmental Compliance Site Inspection/Monitoring Report” (**Appendix 3**).

The sequence and timing of the installation of sedimentation and erosion control measures is critical to their success. Sedimentation and erosion controls shall be installed prior to commencing construction activities that may result in any soil disturbance or cause otherwise polluted site runoff. Inspection of these devices may be required by the National Grid Environmental Scientist or by regulators prior to the start of work. The installation of water bars and other erosion control measures shall be installed shortly thereafter.

3.3 Concrete Wash Outs

Concrete wash outs shall be used for management of concrete waste. Concrete and concrete washout water shall not be deposited or discharged directly on the ground, in wetlands or waterbodies, or in catch basins or other drainage structures. Where possible, concrete washouts shall be located away from wetlands or other sensitive areas. Consult the National Grid Environmental Scientist on proposed concrete wash out locations prior to their use. Following the completion of concrete pouring operations, the wash outs shall be disposed of off-site with other construction debris. Refer to BMPs in **Appendix 4**.

3.4 Construction Activities in Standing Water

The use of silt curtains or turbidity barriers may be required when working in or adjacent to standing water such as ponds, reservoirs, low flowing rivers/streams, or coastal areas. Silt curtains and turbidity barriers prevent sediment from migrating beyond the immediate work area into the resource areas.

Coffer dams constructed using sheet piling or large sandbags (Trade names such as “the Big Bag” or “DamItDams”) may be used to temporarily isolate and contain a work area in standing water.

When working in standing water, an oil absorbent boom, in addition to a silt curtain or other temporary barrier, shall be placed around the work area for spill prevention.


Work in drinking water reservoirs or other waters may require extensive regulatory agency review, even for maintenance work, which could result in additional time required for permitting, review and material procurement prior to the start of work.

3.5 Dewatering

Where excavations require the need for dewatering of groundwater or accumulated stormwater, the water shall be treated before discharge. Appropriate controls include dewatering basins, flocculent blocks, filter bags, filter socks, or weir tanks. Schematics of these BMPs are included in **Appendix 4**. Water trucks or fractionation tanks may be utilized if watertight containers are desired for controlled on-site discharge or for off-site discharge into an approved dewatering area when site restrictions make it difficult to utilize other dewatering methods on-site. Dewatering discharge water shall never be directed into wetlands, streams/rivers, other sensitive resource areas, catch basins, other

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	10 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

stormwater devices, or substation Trenwa trenches. Dewatering flow shall be controlled so that it does not cause scouring or erosion through the use of a dewatering basin, filter sock, or equivalent. If it is determined that the chosen controls are not appropriately filtering the fine sediment from the dewatering pumpate then the National Grid Environmental Scientist shall be notified immediately and the controls shall be revised or supplemented.

When establishing a dewatering basin, consideration should be given to the anticipated volume of water and rate of pumping in determining the size of the dewatering basin. Dewatering basins shall be constructed on level ground. Once pumping commences, the basin shall be monitored frequently to assure that the rate of water delivery to the structure is low enough to prevent water from flowing, unfiltered, over the top of the basin walls. The basin shall be monitored throughout the dewatering process because the rate of filtration shall decrease as sediment clogs the filter fabric. If the basin is not appropriately filtering the fine sediment from the dewatering pumpate then the basin may need to be supplemented with a flocculent block. Field conditions shall dictate how often the basin should be inspected.

Distance to sensitive areas, direction of flow (toward or away from protected, or sensitive areas, such as wetlands, ponds, or streams), amount of vegetative ground cover between the basin and nearby sensitive areas, ground conditions (ledge, frozen, etc.), volume of water being pumped, and pump-rate, are some of the factors to be considered when determining an inspection frequency. Clogged filter fabric shall be replaced and accumulated sediment shall be removed as necessary from the basins to maintain efficacy.

Any new dewatering location (not previously reviewed and approved by the National Grid Environmental Scientist during project planning or permitting) shall be reviewed and the discharge location approved by the National Grid Environmental Scientist before use.

Complex projects that require large scale dewatering shall require individual review by the National Grid Environmental Scientist and may trigger additional permitting.

Dewatering in areas of known chemical contamination may require a separate NPDES permit, or other approval, and treatment or containment system. Consult with the National Grid Environmental Scientist.


3.5.1 Overnight Dewatering

Some projects may necessitate 24-hour dewatering for on-site construction activities. Overnight dewatering will be evaluated on a case-by-case basis by the National Grid Environmental Department.

If it is necessary to conduct overnight dewatering on a project, a dewatering plan must be submitted to the Environmental Department for review and approval **5 business days prior to beginning dewatering activities**. Sufficient knowledge of flow, discharge, and re-infiltration rate of water must be obtained and submitted for review. The Environmental Department

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	11 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

may require monitored dewatering for a period of time in order to provide this data in support of a request for 24-hour dewatering. The dewatering plan must include at a minimum:

1. Location of dewatering system, system components (basin, frac tank, etc), and materials.
2. Location of discharge and distance from closest wetland.
3. Location of erosion controls. A secondary perimeter of erosion controls will be required around the dewatering system for overnight dewatering.
4. Peak flow, discharge rate and re-infiltration rates.
5. Visual monitoring plan for discharge. Expected duration of dewatering.
6. Emergency provisions if overnight, unattended dewatering is proposed.

3.5.2 Dewatering Clean Up/Restoration

Basins shall be cleaned and removed as soon as dewatering is complete. Sediment removed from the dewatering basin shall be allowed to dry before being disposed of by evenly spreading it over unvegetated upland areas where erosion is not a concern if clean or removing it from the site for proper disposal. Off-site trucking of wet soils is prohibited. The sediment disposal area shall be approved by the National Grid Environmental Scientist or the Project Environmental Consultant prior to use. Stabilization measures shall also need to be implemented and approved by the National Grid Environmental Scientist or the Project Environmental Consultant. Soils/sediments shall be dewatered and dried to the point practicable for either on-Site reuse or off-Site transport.

3.6 Check Dams

Check dams are a porous physical barrier installed perpendicular to concentrated storm water flow. They are used to reduce erosion in a swale by reducing runoff energy (velocity), while filtering storm water, thereby aiding in the removal of suspended solids.


Check dams should only be used in small drainage swales that shall not be overtopped by flow once the dams are constructed. These dams should not be placed in streams. Check dams are typically installed in ROWs or on other construction sites prior to the start of soil disturbing work. Per the Rhode Island Soil Erosion and Sediment Control Handbook, no formal design is required for a check dam if the contributing drainage area is 2 acres or less and its intended use is shorter than 6 months; however, the following criteria should be adhered to when specifying check dams.

- The drainage area of the ditch or swale being protected should not exceed 10 acres.
- The maximum height of the check dam should be 2 feet.
- The center of the check dam must be at least 6 inches lower than the outer edges.
- The maximum spacing between the dams should be such that the toe at the upstream dam is at the same elevation as the top of the downstream dam.

Per the NHDES stormwater manual, the use of check dams should be limited to swales with longitudinal slopes that range between 2 to 5 percent that convey drainage from an area less than 1 acre. Existing conditions that exceed these limitations should be assessed in the field and discussed

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	12 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

with the National Grid Environmental Scientist to determine the viability of this BMP for the specific application. Check dams are often comprised of stone, straw bales, sand bags, or compost/silt socks. Use of check dams should be coordinated with the National Grid Environmental Scientist to ensure that the material selection, spacing and construction method are appropriate for the site. Check dams composed of biodegradable materials (e.g. straw bales or wattles, wood chip bags) may require periodic replacement for continued proper functioning¹. Refer to BMPs in **Appendix 4**.

3.7 Water Bars

Water bars should be used on sloping ROWs to divert storm water runoff from unstabilized or active access roads when needed to prevent erosion. Surface disturbance and tire compaction promote gully formation by increasing the concentration and velocity of runoff. Water bars are constructed by forming a ridge or ridge and channel diagonally across the sloping ROW. Each outlet should be stable. The height and side slopes of the ridge and channel are designed to divert water and to allow vehicles to cross. When siting water bars, consideration shall be given to the sensitivity of the area receiving the diverted runoff. For example, runoff should not be directed into a wetland, waterbody, other environmentally sensitive areas, or to private property or public roadways. Refer to BMPs in **Appendix 4**.


3.8 Retaining Walls

In some situations, retaining walls comprised of concrete blocks, gabions, boulders or other comparable materials may be required to stabilize the shoulder of existing access roads and/or supplement required erosion controls. Installation of such measures shall not be allowed as a maintenance activity. Should these controls be considered for a project, it shall be reviewed by the National Grid Environmental Scientist, as design and additional permitting may be required.

3.9 Slope Stabilization

Temporary slope stabilization practices help to keep exposed, erodible soils stabilized while vegetation is becoming established. Acceptable temporary slope stabilization practices may include the use of erosion control blankets, or hydraulic erosion control. Erosion control blankets, often comprised of natural fibers (e.g., jute, straw, coconut, or other degradable materials) are a useful slope stabilization, erosion control and vegetation establishment practice for ditches or steep slopes. Blankets are typically installed after final grading and seeding for temporary or permanent seeding applications. Hydraulic erosion control practices, including Bonded Fiber Matrix or hydroseed with a soil stabilizer (e.g., tackifier and/or mulch) may be an acceptable or desirable alternative form of temporary slope stabilization. For all practices, manufacturer's specifications should be followed for installation depending on slope and other field conditions. Consult the National Grid Environmental Scientist prior to selecting and installing any slope stabilization practices. Refer to BMPs in **Appendix 4**.

¹ Grass growth on a biodegradable type check dam is evidence that the material is decomposing. While this doesn't mean it is no longer functioning, it means it may be in a weakened condition and could potentially fail under high flow velocity. It is acceptable for grass to be growing on a stone check dam.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	13 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

3.10 Maintenance of Sedimentation and Erosion Controls

Sedimentation and erosion controls shall be maintained in good operational condition during the course of the work. This includes, but is not limited to, replacing straw bales that are no longer in good condition, re-staking straw bales, replacing or re-staking silt fence, and removing accumulated sediment. Remove sediment before it has accumulated to one half the height of any exposed silt fence fabric, straw bales, other filter berm, check dams or water bars. Accumulated sediment shall be removed from sedimentation basins to maintain their efficacy. Manage the removed sediment by evenly spreading it over unvegetated upland areas where erosion is not a concern, by stockpiling and stabilizing, or by disposing of off-site. Stabilization measures shall also need to be implemented and approved by the National Grid Environmental Scientist or the Project Environmental Consultant. Where a SWPPP has been prepared for a specific site, the guidelines documented therein shall govern the management of sediment.

4.0 Right-of-Way (ROW) Access

Whenever possible, access shall be gained along existing access routes or roads within the ROW. However, in some cases there is no existing access. In many cases, temporary access can be utilized. The following practices provide general guidance on accessing a ROW. Check with a National Grid Environmental Scientist to determine if any environmental permitting is required before utilizing a temporary access.

Note that the building of new roads or enlargement of existing roads is **prohibited** unless this activity is allowed by a project-specific permit, and the new roads appear on the Site Plans that were authorized in the regulatory approvals.

4.1 Off-ROW Access

Off-ROW access shall be evaluated for wetlands, rare species, cultural resources and other potential sensitive receptors, as applicable. National Grid Real Estate and Stakeholder Relations shall also be contacted as soon as possible once off-ROW access is determined to be needed.


4.2 Stabilized Construction Entrance/Exit for Access to ROWs from Public or Private Roads

A suitable (minimum 15-foot wide by 50-foot long) construction entrance/exit shall be installed at the intersection of the ROW access road/route with public/private paved roads, or other such locations where equipment could track mud or soil onto paved roads. The construction entrance/exit should be comprised of clean stone installed over a geotextile fabric. Geotextile fabric may be omitted for permanent construction entrances/exits on a case-by-case basis with the approval of the National Grid Environmental Scientist. Refer to BMPs in **Appendix 4**.

Construction entrance areas shall be monitored and maintained to ensure that stone or other material is not deposited onto the roadway, causing a safety concern. Where track-out of sediment has occurred onto a roadway, it shall be swept off the road by the end of that same work day.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	14 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

If a construction entrance/exit is clogged with sediment and no longer functions, the sediment and stone may require removal and replacement with additional clean stone (clean stone refreshment) to ensure this tracking pad is performing its intended function adequately. Heavier traffic use may require this clean stone refreshment multiple times throughout a project. Reinforcement of these stabilized construction entrance/exits with asphalt binder or asphalt millings is not likely to be considered “maintenance” and may trigger additional permitting requirements². In some cases, heavily used construction entrances/exits may benefit from the installation of a 5-15 foot strip of asphalt binder or asphalt millings closest to the paved roadway to capture any stone that is tracked from the stone apron. Such cases shall be evaluated on an individual basis with the National Grid Environmental Scientist.

Once work is complete, the construction entrance/exit shall either be removed or retained, depending upon future maintenance-related access needs, property ownership, and/or project-specific approvals. If removed, the area shall be graded, seeded (if adequate root and seed stock are absent) and mulched. Proper approvals for leaving access roads in place shall be obtained; contact the National Grid Environmental Scientist and Property Legal.


4.3 Maintenance of Existing Access Roads

In many cases, the existing access road may need to be maintained to allow passage of the heavy equipment required for scheduled maintenance work. Access roads cannot deviate from the approved and permitted access plans. Maintenance of these roads may include adding clean gravel or clean crushed stone to fill depressions and eroded areas. This activity shall be conducted only within the width of the existing access road footprint and does not include widening existing access roads

If gravel begins to migrate onto the existing vegetated road shoulder, this gravel shall be removed during the project and/or after the completion of use of the road to ensure the road fill is not spreading into adjacent resource areas, or resulting in the road becoming much wider than its pre-existing or permitted condition. In some areas of mapped rare species habitat or other sensitive areas where project-specific permit conditions require the prevention of the migration of sediments into adjacent resources, an engineered stabilization system (e.g., GeoWeb or similar) may be suitable to prevent sedimentation while allowing for unrestricted wildlife migration.

In Massachusetts, any proposed widening of access roads in turtle Priority Habitat would require individual consultation with NHESP and, depending on the level of impact proposed, may require a Project Review filing. The limited filling of ruts or potholes is compatible with the National Grid Operation and Maintenance Plan approved by NHESP under the Massachusetts Endangered Species Act, however, severely rutted access roads in turtle Priority Habitat that require extensive linear feet of stone for safe passage will require individual consultation with NHESP.

² Depending on the road, use of an asphalt binder or asphalt millings as a construction entrance/exit may trigger state or local permit requirements.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	15 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Major reconstruction projects may require multiple permits. In all cases, the fill to be used for existing access roads shall be clean and free of construction debris, trash or woody debris. Use of processed gravel may be approved by the Person-In-Charge and the National Grid Environmental Scientist, on a case-by-case basis. If clean stone is used then addition of more erosion controls may not be necessary.

4.5 Maintenance of Existing Culverts

Damaged culverts may not be repaired or replaced without consulting with the National Grid Environmental Scientist to determine if a permit is required. For functioning culverts, care shall be taken to protect adjacent wetlands and watercourses by installing appropriate sedimentation and erosion controls around the downstream end of the culvert. Culverts shall be repaired/replaced in kind and shall not be changed in size unless approval has been obtained from the National Grid Environmental Scientist. In-kind replacement is replacement using the same material, functional inverts, diameter and length as the existing culvert. Changes to any of these characteristics shall require permitting. Installation of any **new** culvert is not allowed without obtaining all necessary permits first. Refer to BMPs in **Appendix 4**.

If, at the time of anticipated replacement, there is heavy flow through the culvert, the Person-In-Charge shall consult with the National Grid Environmental Scientist, to verify whether the culvert shall be replaced at that time. Water may need to be temporarily diverted during culvert repair/replacement. There typically are seasonal restrictions limiting both the replacement of existing culverts as well as installation of new culverts to the low-flow period. The low-flow period can vary from state to state. If any unexpected conditions are encountered during culvert replacement, the National Grid Environmental Scientist shall be contacted immediately prior to the work being completed for additional consultation.

4.6 Temporary Construction Access over Drainage Ditch or Swale


In some situations, construction access from paved roads onto ROWs may require the crossing of drainage ditches or swales along the road shoulder. In these situations, the installation of construction mats, mat bridges or temporary culverts may facilitate construction access over the ditches or swales. These culverts shall be temporary only, sized for peak flow, and shall be removed after construction is complete. Consult with the National Grid Environmental Scientist prior to installation. In addition, if access over existing culverts may require extending the culvert, consult with the National Grid Environmental Scientist. Refer to BMPs in **Appendix 4**.

4.7 Construction Material along ROW

After preparing a site by clearing and/or installing any necessary erosion and sediment controls and prior to the start of construction, material such as poles, cross-arms, cable, insulators, stone and other engineered backfill materials may be placed along the ROW, as part of the project. The stockpiling of stone and other unconsolidated material on construction mats shall be avoided, if determined necessary due to access and work pad constraints, the material must be placed on a geotextile fabric and be properly contained with a sedimentation barrier such as straw wattle. No construction material shall be placed in wetlands or other sensitive resource areas unless authorized by the National Grid Environmental Scientist or Project Environmental Consultant.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	16 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

5.0 Winter Conditions

5.1 Snow Management

Refer to **Appendix 6** for the current Snow Disposal Guidelines.

5.2 De-Icing

Where allowed, calcium chloride is preferred as a de-icing agent when applied according to manufacturer's guidelines in upland areas. Sand shall be used on construction mats through wetland areas.

Consult with the National Grid Environmental Scientist on de-icing agents when working in a facility or substation close to resource areas. Many municipalities have specific requirements for de-icing agents allowed within 100 feet of wetland resources and other sensitive areas.

5.3 Snow and Ice Management on Construction Mats


Proper snow removal on construction mats shall avoid the formation of ice. To avoid the formation of ice, snow shall be removed from construction mats before applying sand. Prior to their removal from wetlands, sand shall be collected from the construction mats and disposed of in an upland area. A round street sweeping brush mounted on the front of a truck may be an effective way to remove snow from construction mats. Propane heaters may also be suitable solutions for snow removal and/or de-icing of construction mats.

Once construction mats are removed, wetlands shall be inspected for build up of sand that may have fallen through construction mats. Care shall be taken to inspect wetland crossings as each mat is removed to ensure sand is properly removed and disposed of off-site.

6.0 Construction Mats

The use of construction mats allows for heavy equipment access within wetland areas. The use of construction mats minimizes the need to remove vegetation beneath the access way and helps to reduce the degree of soil disturbance and rutting in soft wetland soils. Construction mats most often used by National Grid are wooden timbers bolted together typically into 4-ft by 16-ft sections, wooden lattice mats, or composite mats. In some cases, construction mats or other mats are used for staging or access in upland areas based on site conditions (e.g., agricultural field access). Refer to BMPs in **Appendix 4**.

Typically construction mats may be installed on top of the existing vegetation, however in some instances cutting large woody vegetation may be required. Check with National Grid Environmental Scientist prior to cutting or clearing vegetation for construction mat placement.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	17 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Where an extended period of time has lapsed since wetland delineation and start of construction, and new vegetative growth has concealed wetland flagging or flagging is simply no longer obviously visible, wetland boundaries should be re-flagged where necessary prior to the installation of matting.

Follow the approved plans in the EFI for construction mat installation and do not deviate from the plans. **Any deviation from the approved plans needs to be communicated immediately to the National Grid Environmental Scientist as it may require additional permitting, require stopping the project or result in a permit violation or revocation.**

6.1 Construction Mats and Mowing

Close coordination with the mowing contractor shall be required to ensure that access plans are followed, and construction mats are utilized when necessary. Sometimes mowing contractors may have to work off the leading edge of a construction mat to mow in order to lay the next construction mat and continue further into the wetland. Under no circumstances shall trees or shrubs be allowed to be pulled out of the wetland by the root ball. The root ball of trees and shrubs shall remain intact. Chipping debris and excessive amounts of slash shall not be placed in wetlands or other resource areas. In some instances, it may be beneficial to pile a reasonable amount of slash within a nearby upland area to create habitat for wildlife. This activity shall be approved by the National Grid Environmental Scientist.


6.2 Stream Crossings and Stream Bank Stabilization

Stream crossings shall be bridged with construction mats or other temporary minimally-intrusive measures unless fording is acceptable for the site and is authorized by the National Grid Environmental Scientist. Care shall be taken when installing a construction mat bridge to insure that the stream bed and banks are not damaged during installation and removal and that stream flow is not unduly restricted. Where stream width allows, construction mats shall be installed to span the watercourse in its entirety without stringer placement in the water or any restriction of stream flow. Environmental permits may be required to cross or disturb protected waters, depending upon state-specific regulatory requirements. Refer to BMPs in **Appendix 4**. Immediately following construction mat removal, all stream banks shall be stabilized and restored to prevent sedimentation and erosion.

6.3 Cleaning of Construction Mats

Mats shall be certified clean by the vendor prior to installation. The vendor shall use the certification form provided as **Appendix 5** to document compliance. Clean is defined as being free of plant matter (stems, flowers, roots, etc), soil, or other deleterious materials prior to being brought to the project site. Any equipment or timber mats that have been placed or used within areas containing invasive species within the project site shall be cleaned of plant matter (stems, flowers, roots, etc), soil, or other deleterious materials at the site of the invasive species prior to being moved to other areas on the project site to prevent the spread of invasive species from one area to another³. **Mats shall be cleaned prior to being removed at the completion of the project: exceptions to this requirement**

³ On ROW projects where multiple wetlands may be dominated by the same invasive species, cleaning may not be required for movement along the ROW. Check with the National Grid Environmental scientist for guidance.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	18 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

may be made on a case-by-case basis. Consult with the National Grid Environmental Scientist prior to discharging or disposing of any waste water or waste material from the cleaning of construction mats.

6.4 Stone Removal for Construction Mat Placement

For situations where the matting contractor determines that stones or boulders must be removed or relocated within wetland areas in order to install safe and level structure work pads or access roads the boulders shall be moved in a manner which does not result in significant soil disturbance (i.e., pushing with a bull dozer is not allowed). The boulders shall not be placed on any existing vegetated areas within wetlands or within vernal pools. When numerous boulders shall be removed from a wetland area, they shall be deposited in an upland area outside of the flagged wetland limits, outside of any cultural resource areas and outside of any RTE species populations. Any boulders that shall be placed within buffers (In MA, the 100-foot buffer zone, and in RI, the 50-foot Perimeter Wetland, 100-foot or 200-foot Riverbank Wetlands) shall be placed to avoid causing soil disturbance and they shall be within an approved limit of work. When there is a significant number of boulders that need to be removed, the National Grid Environmental Scientist shall be consulted for guidance.

6.5 Transition onto Mats

Erosion controls and stone or wood chip ramps shall be installed to promote a smooth transition to and minimize sediment tracking onto construction mats. Geotextile may be added beneath stone or wood chip transitions to facilitate removal, as necessitated by site or permit conditions. Mat transitions shall be removed once construction mats have been removed and during restoration. Refer to BMPs in **Appendix 4**.

6.6 Construction Material on Mats


The stockpiling of stone, drill spoils and other unconsolidated material on construction mats shall be avoided unless determined necessary due to access and work pad constraints. Additional controls, such as watertight mud boxes and geotextile/filter fabric over or between construction mats shall be considered for stockpile management. If material is placed on construction mats and falls through into wetlands, the material must be removed by hand. Saturated soils shall be allowed to dewater prior to off-site transport for sufficient time to ensure that water/sediment is not deposited onto construction mats or public roads during transport. Heavy machinery shall not be left overnight on mats located within floodplain unless approved by the National Grid Environmental Scientist, the machinery is still in use, and removal of the equipment requires the use of additional equipment to move it and would increase vehicle trips in/out of wetlands. In these situations and when approved by the National Grid Environmental Scientist, the equipment shall be secured against vandalism and secondary containment measures shall be employed where feasible. Mat anchoring shall be evaluated, see below.

6.7 Mat Anchoring

The National Grid Environmental Scientist and Project environmental consultant shall indicate to the project team when mat anchoring may or shall be necessary. The matting contractor will propose the method of mat anchoring, which will be approved by the National Grid Environmental Scientist and the

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	19 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

National Grid Construction Supervisor. The need for anchoring should be noted in the project EFI, on the project access and matting plans, and in the scope of the bid document (if externally sourced).

Anchoring of construction mats should be considered when any of the following conditions are presented at a project work location:

Location	Considerations
Stream crossings Shorelines of Ponds/Lakes Wetlands Floodplains	When located in a mapped flood area (A). When mapped 100-year flood elevations (AE) are greater than 2 ft above existing grades. Where past flash flood events have occurred. Where steep terrain is present or surrounds the project location. When mats will be in place during hurricane season for greater than 2 weeks.
Tidal areas	When located in a Velocity (V or VE) Zone. When mats will be in place during a moon tide cycle. When mats will be in place during hurricane season for greater than 2 weeks.

Examples of mat anchoring are provided below, but the implementation methods for anchoring mats are not limited to these examples. Where anchoring is determined to be necessary, the matting contractor should propose a method suitable based on field conditions and that takes crew safety, slip/trip/fall hazards, size of matting footprint, and other project and site-specific factors into consideration. Refer to BMPs in **Appendix 4**.

Limited sets of mats

- Cable or rope in chain pockets and run linearly, or
- Linear ropes anchored using helical screws, manta ray anchors, or posts.

Larger sets of mats or those without chain pockets


- Chain link fence posts or other posts driven in along mat edge every 3-4 feet and ropes then laced across mats between opposing posts before storm event, or
- Anchor bolts added to mats, then cable is laced between bolts and tied to helical or manta ray anchor.

6.8 Corduroy Roads

Corduroy roads are a wetland crossing method where logs are cut from the immediate area and used as a road bed to prevent rutting from equipment crossing. This technique is designed to be used in areas of wetland crossings where there is no defined channel or stream flow and should never be used in streams. Corduroy logs shall be placed in the narrowest area practicable for crossing with the logs

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	20 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

placed perpendicular to the direction of travel across wet area. The use of corduroy logs shall only be in emergencies when approved by the National Grid Environmental Scientist or when they have been specifically permitted as part of a project. Refer to BMPs in **Appendix 4**.

6.9 Construction Mat Removal

Once construction mats are removed, wetlands shall be inspected for build up of sand or other materials that may have fallen through construction mats. Care shall be taken to inspect wetland crossings as each mat is removed to ensure any materials are properly removed and disposed of off-site.

6.10 Utility Air Bridging

In ROWs where other utility facilities (including but not limited to gas, oil, fiber optic, electric, water, and sewer) are co-located within the transmission ROW, bridging may be required to cross those facilities. The project team shall coordinate with the respective utility company prior to determining if bridging or permanent crossings are required.


7.0 LGP Equipment Use

Only when approved by the National Grid Environmental Scientist on a case-by-case basis shall equipment with a LGP **psi that meets the state-specific USACE General Permit requirement when loaded** be allowed to access through wetlands. Refer to the state-specific General Permit for the definition of LGP in each state at: <http://www.nae.usace.army.mil/Missions/Regulatory/State-General-Permits/>, or to the summary table provided below. The National Grid Environmental Scientist's approval of the use of LGP equipment through wetlands depends on several criteria including:

- Time of year. LGP equipment use may be allowed if weather and field conditions at the time of construction are suitable to eliminate/minimize the concern of rutting or other impacts. Frozen, frozen snow pack, low flow, drought conditions, or unsaturated surface soil conditions are typically acceptable conditions. Spring and fall construction, due to the typical higher precipitation, are not suitable times of year for LGP equipment use.
- Number of trips. Multiple trips through a wetland have shown to increase the potential for damage and require matting. LGP equipment use shall likely only be approved if trips are limited to one trip in and one trip out.
- Type of wetland system. Some wetlands have harder soils/substrate, and may be passable without causing significant damage. Some of the wetlands along National Grid ROWs have existing hard bottom roads that have been vegetated over time and may be traversed with LGP equipment without construction mats.
- Emergencies. LGP equipment use may be allowed during emergency or storm conditions for outage restoration.
- State-specific USACE General Permit Performance Standards. The standard is for no impact to the wetland, which may be obtained by using LGP equipment **when loaded**). *"Where construction requires heavy equipment operation in wetlands, the equipment shall either have low ground*

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	21 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	


pressure (as specified in the USACE GP), or shall not be located directly on wetland soils and vegetation; it shall be placed on construction mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation.”

- Local bylaws. Municipal wetland bylaws, where applicable, shall be reviewed for prohibitive conditions or applicable performance standards.

LGP equipment is prohibited in the following resources areas:

- Stream crossings
- State listed-species habitat
- Outstanding Resource Waters (ORWs)
- Vernal pools
- Archaeological sensitive areas

Where LGP equipment use is desired in lieu of construction mats, the construction supervisor should identify these areas on marked-up access plans. A site visit with the Project Environmental Monitor should be scheduled to assess if the proposed locations are potential candidates. The Project Environmental Monitor will document potentially suitable locations and dismiss others as unsuitable.


 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	22 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

ACOE New England District General Permit Requirements

State	Restrictions	Maximum PSI (when loaded) for Use without Mats	Reference
MA	<i>One of the following must apply:</i> Equipment operated within wetlands shall: a) Have low ground pressure; b) Be placed on timber mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation; or c) Equipment must be operated on adequately dry or frozen conditions such that shear pressure does not cause subsidence of the wetlands immediately beneath equipment and upheaval of adjacent wetlands.	3 psi	MA General Permit, General Condition 13
NH	<i>One of the following must apply:</i> Equipment operated within wetlands shall: a) Have low ground pressure; b) Be placed on timber mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation; or c) Be operated on frozen wetlands.	4 psi	NH General Permit, General Condition 17
VT	<i>One of the following must apply:</i> Equipment operated within wetlands shall: a) Have low ground pressure; b) Be placed on timber mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation; or c) Be operated on frozen wetlands such that shear pressure does not cause subsidence of the wetlands immediately beneath equipment and upheaval of adjacent wetlands. Note: Written authorization from the Corps required to waive the use of mats during frozen or dry conditions.	3 psi	Vermont General Permit, General Condition 14
RI	<i>One of the following must apply:</i> Equipment operated within wetlands shall: a) Have low ground pressure; b) Be placed on timber mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation; or c) Be operated on frozen wetlands such that shear pressure does not cause subsidence of the wetlands immediately beneath equipment and upheaval of adjacent wetlands.	6 psi	Rhode Island General Permit, General Condition 15

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	23 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

State	Restrictions	Maximum PSI (when loaded) for Use without Mats	Reference
	Note: Written authorization from the Corps required to waive the use of mats during frozen or dry conditions.		

Due to the fact that ground conditions may change between the time of the evaluation and construction, LGP equipment approval is required **at the time of construction for each wetland crossing** and shall be dependent upon the above conditions. In addition, LGP equipment use and approval shall be assessed by the National Grid Environmental Scientist or Project Environmental Monitor during construction on a continuing basis

Once a location is approved for the use of LGP equipment:

- The Construction Supervisor must check-in with the Project Environmental Monitor at least two weeks before construction begins to ensure conditions remain suitable for LGP equipment use, and weather conditions are favorable.
- The Project Environmental Monitor must observe the equipment when in use.
- LGP equipment use shall cease immediately if field conditions are found to be unsuitable (i.e. soil rutting greater than six inches or the destruction of vegetation root systems beyond the capacity of natural revegetation).
- **If wetlands damage occurs, the use of the LGP equipment shall be suspended, and the wetlands be restored.**
- Any LGP equipment used within areas containing invasive species within the project site shall be cleaned of plant matter (stems, flowers, roots, etc), soil, or other deleterious materials at the site of the invasive species prior to being moved to other areas on the project site to prevent the spread of invasive species from one area to another.

8.0 Soil Disturbing Activities

8.1 Dust Control


Cutting activities shall be conducted to minimize the impacts of dust on the surrounding areas. Dust suppression is an important consideration. Water or other National Grid approved equivalent in accordance with the manufacturer's guidelines may be used for dust control along ROWs in upland areas. During application of water for dust control, care shall be taken to ensure that water does not create run-off or erosion issues. Refer to BMPs in **Appendix 4**.

8.2 Clearing

Clearing is not allowed without specific permission as it constitutes soil disturbance under several regulatory programs and may trigger permitting by increasing the project's footprint of disturbance. If clearing is required for a project, the limit of clearing shall be established with flagging or construction

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	24 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

fencing and/or erosion controls. Clearing shall be done in accordance with project specific permits. Following the completion of clearing, the limits of work shall be re-established. Refer to BMPs in **Appendix 4**.

8.3 Grubbing

Grubbing is not allowed without specific permission as it constitutes soil disturbance under several regulatory programs and likely triggers permitting by increasing the project's footprint of disturbance. If grubbing is required for a project, the limit of grubbing shall be re-established after clearing has been completed. The area of grubbing shall be identified with flagging or construction fencing and/or erosion controls. Grubbing shall be conducted in accordance with project-specific permits.

8.4 Blasting, Noise and Vibration Control

If blasting is anticipated, the project team, including the National Grid Environmental Scientist, shall be consulted. If possible, plan work in residential areas to avoid noisy activities at night, weekends or during evenings. Emergency work in residential areas should be carried out in such a way as to keep noise to a minimum at night and weekends. Equipment should be maintained as per the manufacturer's guidance to minimize noise and vibration.

Work plans must consider local noise ordinances and provide specific controls to ensure noise levels are maintained within specified limitations.

8.5 Site Grading


The work site shall not be graded other than in accordance with project permits. Any proposed grading shall be reviewed by the National Grid Environmental Scientist for wetlands, rare species habitat, areas of cultural and historical significance, and other environmentally sensitive areas prior to start of work. In some cases, additional testing for cultural or historical resources may be triggered by proposed grading; alternatives to grading may be sought due to protracted time frame of obtaining the permit associated with testing and performing the testing. Grading outside of a regulated area shall be kept to the minimum extent necessary for safe and efficient operations and shall comply with the project permit plans.

Grading shall be performed in a manner which does not increase the erosion potential at the Site (e.g., terraces or slope interruptions shall be utilized). Graded sites shall be promptly stabilized by applying a National Grid approved seed mix (if adequate root and seed stock are absent), and mulching with hay, straw or cellulose (use straw or cellulose hydromulch where the potential introduction of invasive plant species is of concern) to reduce erosion and visual impact, as soon as possible following completion of work at the site. Grading within a regulated area shall be subject to the review and approval of the National Grid Environmental Scientist.

In some municipalities, site grading activities require the prior approval of the Town Engineer, Building and Zoning Official, or Public Works Director. Local ordinances or bylaws should be reviewed for applicable restrictions and permitting thresholds

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	25 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

8.6 Grounding Wells

The installation of grounding wells shall require erosion controls and proper soil management. Due to the typical depth required for grounding wells (typically 50 to 200 feet or more), erosion controls shall be installed around the proposed well location when working in buffer zone, in proximity to sensitive resources or near slopes. Also, dewatering basins may be required for the proper management of groundwater. The National Grid Environmental Scientist shall be consulted for the disposal of any excess soil.

8.7 Counterpoise and Cathodic Protection

The installation of counterpoise or cathodic protection shall require erosion controls and proper soil management. The National Grid Environmental Scientist shall be consulted for the disposal of any excess soil.

8.8 Work Pads

When work pads are being constructed, only clean material shall be used in their construction. Work pads shall only be constructed in areas approved by the National Grid Environmental Scientist and shown on the approved permit access plans.

8.9 Site Staging and Parking

During the project planning and permitting process, locations shall be identified for designated crew parking areas, material storage, and staging areas. Where possible, these areas should be located outside of buffer zones, watershed protection areas, and other environmentally sensitive areas. Any proposed locations shall be evaluated for all sensitive receptors and for new projects requiring permitting, shall be incorporated onto permitting and access plans.

8.10 Soil Stockpiling

Soil stockpiles shall be located in upland areas and, if in close proximity to wetlands and wetland buffers, shall be enclosed by staked straw bales or another erosion control barrier. The stockpiling of stone, drill spoils and other unconsolidated material on construction mats shall be avoided unless determined necessary due to access and work pad constraints. Additional controls, such as watertight mud boxes and geotextile/filter fabric over or between construction mats shall be considered for stockpile management. If material is placed on construction mats and falls through into wetlands, the material must be removed by hand. Saturated soils shall be allowed to dewater prior to off-site transport for sufficient time to ensure that water/sediment is not deposited onto construction mats or public roads during transport.


8.11 Top Soil/High Organic Content Soil

When the work site requires excavation and grading, the top soil shall be stockpiled separately from the material excavated. This top soil shall be spread as a top dressing over the disturbed area during restoration of the site.

In some instances where work is occurring within wetlands, high organic content soil may be displaced. Such high organic content soil shall be segregated from other excavated materials and stockpiled for

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	26 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

use in wetland restoration areas. Care shall be taken to minimize the handling of high organic content soil. Preferably, the soil shall be stockpiled in one location until it is moved to the restoration area.


9.0 Stone Wall Dismantling and Re-building

Removal or alteration of stonewalls shall be avoided, whenever possible. As appropriate, some stonewalls removed or breached by construction activities shall be repaired or rebuilt. Rebuilt stone walls shall be placed on the same alignment that existed prior to temporary removal, to the extent that it shall not interfere with operations. The removal and rebuilding of stone walls requires approval from the National Grid Environmental Scientist and Property Legal, and may require several weeks lead time for coordination. Note that not all states allow this technique and that dismantling may not be allowed at all due to quality or significance of the wall. Once a stone wall has been identified as requiring dismantling, the following procedures shall be followed:

- Identify stone wall that is required to be temporarily dismantled and notify project team that a site visit is warranted to review the stone wall.
- The National Grid Environmental Scientist, with support from Property Legal and/or cultural/historical consultant, shall determine if permitting or additional permissions are required prior to dismantling stone wall.
- Once permit or permissions have been received, full documentation of wall dimensions (measurements and photographs) shall be submitted to the National Grid Environmental Scientist. Documentation of the wall dimensions shall be marked onto a copy of the applicable EFI access plan (or equivalent plan) with a useful reference for future locating such as GPS coordinates and/or measurement from a permanent reference point (closest structure location or closest cross street, etc.). The wall shall be photographed from all sides with a written description of the photograph (i.e. southern side of wall looking north). In addition, documentation of the length of wall to be dismantled shall be recorded. Take special care to note if granite property bounds (or other marker) are located within the wall so additional survey can be accomplished prior to dismantling in cases where the stone wall represents a property boundary. Site visits by project team (which shall include the National Grid Environmental Scientist) are a mandatory requirement prior to dismantling.
- No dismantling shall take place until documentation has been submitted to the National Grid Environmental Scientist and approved as sufficient documentation.
- Stones from the wall shall be removed from the work area and temporarily stored in nearby location, away from wetlands; buffer zones; rare species habitat and other historical/archeological concerns.
- Avoid dismantling via the “bulldozer” method when possible as this method makes it nearly impossible to rebuild the wall in the same alignment due to its uncontrolled nature. Dismantling shall be conducted either by hand, with stones stacked as they are removed, or on less “sensitive” walls to use an excavator with a thumb to grab each stone and build a stockpile. Significant ground disturbance below the wall shall be avoided.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	27 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

- Once construction and access in the area has been completed, the wall shall be rebuilt to pre-dismantled conditions or better. If rebuilding a stone wall can not be placed on the same alignment that existed prior to temporary removal, approval from the National Grid Environmental Scientist and Property Legal is required. **Note that if the wall represents a legal property boundary or is historically or culturally significant (or was previously determined to be in a very high quality condition), a professional stone masonry company may be required to document wall alignment, and conduct the dismantling and rebuilding.**

10.0 Avian Nest Removal

Avian nest removal shall be done in accordance with EG-304. Consult the National Grid Environmental Scientist prior to removing any nests. There are seasonal restrictions of the removal of avian nests and federal or state permits may be necessary prior to removal.


11.0 Drilling Fluids and Additives

When installing subsurface structures, there may be a need to utilize drilling aids such as slurries, borehole sealants, and other additives. All necessary steps shall be taken by National Grid personnel and contractors to prevent potential adverse effects on drinking water aquifers, groundwater quality, and wetlands when utilizing drilling aids. Efforts should be made to utilize natural bentonite clay-type materials, in place of polymer-based drilling aids. Regardless of the specific product type, the following requirements shall be met:

- Drilling aids must be NSF certified and manufactured to NSF-ANSI 60 standards. https://www.nsf.org/newsroom_pdf/NSF-ANSI_60_watemarked.pdf
- Product use must be in accordance with manufacturer's specifications and instructions.
- National Grid personnel or their contractor shall provide all the necessary information regarding the proposed product to be used to National Grid's Environmental Sustainability, Compliance and Licensing & Permitting Department as early as possible in the project planning phase. If the work is being performed by a contractor, this information must be included as part of their initial bid package.
- If polymer-based products are proposed for use, product information shall be included in all related environmental regulatory filings and frac-out plans, if possible.
- A qualified individual shall be designated who will confirm/verify and document the specific use of a drilling aid at each location. This will include add-mix ratios, surface area treated, volume of water within excavation, volumes/weight of additives used, and any other measurements specified by the manufacturer. No mixing will be allowed in the drilled shaft excavation.
- The Contractor or National Grid crew performing the work is responsible for neutralizing all drilling products, as applicable, in accordance with the manufacturer's specifications. This shall be performed following removal from the excavation and while held in holding tanks. A

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	28 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

qualified person shall be designated by the Contractor who will confirm/verify and document the appropriate neutralization activity at each location, as necessary.

- Waste drilling aids (neutralized or not) or soils that may have come into contact with drilling aids will not be disposed of on National Grid properties, discharged to any ground surface or subsurface, waterbodies, wetlands or placed on 3rd party properties.
- All product use must be completed in strict adherence with the management, storage, mixing, transporting, disposing and any other requirements of state and federal regulatory approvals and permits, as applicable.
- Relevant documentation shall be maintained by the Contractor or National Grid crew performing the work, and shall include volume of material treated and disposed and the location/facility at which it was disposed.
- National Grid will not be identified as the disposal generator for any polymer based slurry waste or additives generated by Contractor activities.
- The Contractor or National Grid crew performing the work assumes full responsibility for the safe storage of all polymers and additives during use and also assumes full responsibility for improper use and application of said polymers and additives that are deemed to have contravened aquifer and/or groundwater quality.
- National Grid reserves the right to refuse and terminate the use of any specific drilling aid at any time.

Regardless of the type of drilling aid utilized, the Contractor or National Grid crew performing the work is responsible for properly treating, containerizing, testing, transporting and disposing of any/all fluids and solids generated during their activities. All wastes must be disposed of in accordance with federal and state regulations. Relevant documentation shall be maintained and shall include volume of material treated and disposed and the location/facility at which it was disposed.


12.0 Water Withdrawal for Geotechnical Investigations

The use of water during geotechnical drilling operations may be required, and is most common during the “drive and wash” drilling technique, where 4- or 6-inch diameter casing is driven into the ground, and the soil inside the casing is washed out using a pump and hollow rods. Soil samples are generally collected at periodic intervals using a split spoon sampler (e.g., every 5 vertical feet).

The National Grid Environmental Scientist and/or Project Environmental Monitor may approve withdrawals from wetlands and waterways on a case-by-case basis should the geotechnical team advise no other options are available. Generally, the amount of water required for withdrawal is between 100 and 200 gallons, and the water is then recycled continuously in the drilling process. Certain scenarios may require additional water usage if water is lost down the boring (e.g., lost due to bedrock fractures during rock coring). The following general guidance should be adhered to when determining whether water withdrawals may be allowed during geotechnical investigations on the ROW. Approval from the National Grid Environmental Scientist and/or Project Environmental Monitor is required prior to initiating water withdrawals during geotechnical investigations.

Approved for use per EP – 10, Document Control.


PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	29 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

- Withdrawals from perennial streams, ponds, lakes and large wetlands systems are preferred over small isolated wetlands to ensure the water level, water table, and hydroperiod are not affected. Prior to start of work, the Contractor shall identify which water source they prefer to withdraw from. The National Grid Environmental Scientist and/or the Project Environmental Monitor will confirm whether these sources are appropriate.
- Care should be taken to avoid alteration of wetlands or the beds and banks of surface waters. Examples of alterations include, but are not limited to, the following:
 - (a) the changing of pre-existing drainage characteristics, flushing characteristics, salinity distribution, sedimentation patterns, flow patterns and flood retention areas;
 - (b) the lowering of the water level or water table;
 - (c) the destruction of vegetation; and
 - (d) the changing of water temperature, biochemical oxygen demand (BOD), and other physical, biological or chemical characteristics of receiving waters.
- Wetlands and waterways providing habitat for rare species should be avoided unless all other options are exhausted. Under no circumstances should water be withdrawn from a Vernal Pool.
- Withdrawal pipes or stingers should be elevated off the bottom of wetlands and streams during the duration of pumping. Additionally, fabric or screening should be covering the withdrawal pipes to eliminate inadvertent harm to wildlife.
- Withdrawals should be performed in a manner that does not damage vegetation, disturb sediment, or result in the release of temporary or permanent fill material (e.g., sediment, spoils, or turbid water) into the wetland/waterway. Additional detail from geotechnical experts may be required to solidify BMP recommendations.
- Any water used for geotechnical drilling operations (including water withdrawn from surface water, brought on-site, or from other sources) shall be discharged into the open borehole or to an upland area such that the water infiltrates to the ground and is not discharged to a wetland or surface water resource area. Consultation with the National Grid Environmental Scientist and/or the Project Environmental Monitor is required if this is not feasible. At no time should water withdrawals result in a temporary or permanent fill/discharge of material (e.g. sediment, spoils, or turbid water) into the wetland or waterway.
- If water sourcing options is not determined prior to mobilization, necessary water shall be brought in by tank truck. Should withdrawal from surface water sources become necessary during soil boring work, the National Grid Environmental Scientist and/or the Project Environmental Monitor shall be notified prior to beginning withdrawal. If initial withdrawal from surface water is approved by the National Grid Environmental Scientist and/or the Project Environmental Monitor, the driller may withdraw from the surface water, as long as the above criteria are met.
- If excessive water withdrawal is necessary, the National Grid Environmental Scientist and/or the Project Environmental Monitor shall be consulted to determine whether the water source is appropriate for withdrawal.
- In New Hampshire, withdrawals made from state-owned property require written permission from

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	30 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

the agency with primary responsibility for monitoring and/or maintaining the site.

13.0 Gates

When not in use, gates shall be locked with a company-approved lock or double locked with the property owner's lock. New gates may be installed during a project, however, installation of a gate requires permission from the property owner, and may require environmental permitting. Consult with National Grid Real Estate and the National Grid Environmental Scientist prior to installing a new gate, as well as with the appropriate engineering department for the current company gate specifications. Refer to BMPs in **Appendix 4**. Installation of ROW access restrictions (e.g., stone, bollards, other) at road crossings also require consultation with the National Grid Environmental Scientist and Property Legal.

14.0 Signage

Specific signage may be required by permits or be specified in the EFI to limit access in certain sensitive areas. Signs shall be used to clarify allowed access and sensitive areas, such as:

- "No snow stockpiling beyond this point";
- "Approved access (to structures A-F)";
- "Do not cross this area until construction mats are in place";
- "No vehicle crossing";
- "Areas to avoid"; and
- "Environmentally Sensitive Area – Keep Out."

Signs shall be used in conjunction with snow fencing or other physical barriers as demarcation for sensitive areas (e.g., rare species areas, sensitive archeological locations, etc.) that need to be protected and avoided by construction activities. In addition, permit signs required by the regulatory agencies shall be present (i.e. MADEP, RIDEM, EPA (SWPPP), ACOE, etc) at construction sites and/or ROW access points. Construction signage shall be installed and maintained by the contractor performing the work during the project. Absence of signage does not eliminate the need to comply with access plans, permit conditions, and other regulatory requirements. Refer to BMPs in **Appendix 4**.


15.0 Refueling and Maintenance Operations

15.1 Spill Prevention and Response Plan

Spill controls shall be provided on every field vehicle. Bulk storage of fuels (55 gallons or greater) shall be approved by the National Grid Environmental Scientist prior to being brought on site. The need for a field spill plan shall be evaluated specific to the project for regulatory requirements under SPCC regulations or local ordinances. A field spill plan would include information on fuels and oils being used, approximate amounts in each container or type of equipment, location, fueling location, secondary containment, response and notification procedures, including contact phone numbers, etc. All

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	31 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

personnel shall be briefed on spill prevention and response prior to the commencement of construction. The state-specific EI-501 and EG-502 shall be followed in the event of a spill.

Typical construction activities do not require the use or storage of large quantities of oil or hazardous materials (i.e., greater than 55 gallons). However, oil and/or hazardous materials (OHM) may be required in limited quantities to support construction or vehicle operations. Best practices shall be followed in the use and storage of OHM which include but are not limited to: storage and refueling greater than 100 feet from resource areas; maintenance of spill response equipment at work locations sufficient to handle incidental releases from operating equipment; general training for on-site personnel for spill clean up response for incidental releases of OHM; and contracting with an on-call spill response contractor that is capable of managing incidental and significant releases of OHM. There may situations that additional precautions shall be required for the storage or use of OHM (i.e., within wellhead protection areas, GA/GAA areas, Zone IIs). Storage of OHM shall be done in accordance with any applicable regulatory requirements.

15.2 Field Refueling

Small equipment such as pumps and generators shall be placed in small swimming pools or on absorbent blankets/pads, to contain any accidental fuel spills. Small swimming pools with absorbent blankets/pads, and/or other secondary containment, shall be used for refueling of fixed equipment in wetlands and should be maintained to prevent accumulation of precipitation.

15.3 Grease, Oil, and Filter Changes

Routine vehicle maintenance shall not be conducted on project sites.


15.4 Other Field Maintenance Operations

When other vehicle or equipment maintenance operations (such as emergency repairs) occur, company personnel or contractors at field locations shall bring vehicles or equipment to an access location a minimum of 100 feet away from environmentally sensitive areas (e.g., wetlands or drinking water sources). A paved area, such as a parking lot or roadway, is a preferred field maintenance location to minimize the possibility of spills or releases to the environment.

Crews shall take all usual and reasonable environmental precautions during repair or maintenance operations. Occasionally, it is infeasible to move the affected vehicle or equipment from an environmentally sensitive area to a suitable access area. When this situation occurs, precautions shall be taken to prevent oil or hazardous material release to the environment. These precautions include (but are not limited to) deployment of portable basins or similar secondary containment devices, use of ground covers, such as plastic tarpaulins, and precautionary placement of floating booms on nearby surface water bodies.

15.5 Tools and Equipment

Cleaning of tools and equipment shall be conducted away from environmentally sensitive areas (such as wetlands, buffer zones or drinking water sources) to the maximum extent possible. A paved area such

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	32 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

as a parking lot or roadway is preferred, to minimize the possibility of spill or release to the environment. Crews shall wipe up all minor drips or spills of grease and oil at field locations.

16.0 Stabilization Deadlines for Projects Subject to EPA Construction General Permit

16.1 Deadlines to Initiate Stabilization Activities (Permanent and Temporary)

Soil stabilization measures shall be implemented immediately whenever earth-disturbing activities have permanently or temporarily ceased on any portion of the project. The following are some examples of activities that constitute initiation of stabilization:

- Preparing the soil for vegetative or non-vegetative stabilization;
- Applying mulch or other non-vegetative product to the exposed area;
- Seeding or planting the exposed area;
- Finalizing the arrangements to have stabilization product fully installed in compliance with the deadlines to complete stabilization in Section 15.2 below.

16.2 Deadlines to Complete Stabilization Activities (Permanent and Temporary)

As soon as practicable, but no later than 14 calendar days or 7 calendar days (for areas discharging to a sensitive water) after the initiation of soil stabilization measures commence the following should be completed:

- For vegetative stabilization, all activities necessary to initially seed or plant the area to be stabilized; and
- For non-vegetative stabilization, the installation or application of all such non-vegetative measures.

16.3 Vegetative Stabilization (all except for arid, semi-arid, or on agricultural lands)


- Provide established uniform vegetation (e.g., evenly distributed without large bare areas), which provides 70% or more of the density of coverage that was provided by vegetation prior to commencing earth-disturbing activities. Avoid the use of invasive species as cover.
- For final stabilization, vegetative cover must be perennial; and
- Immediately after seeding or planting a disturbed area to be vegetatively stabilized, a non-vegetative erosion control must be implemented to the area while the vegetation is becoming established. Examples include; mulch and rolled erosion control products.

16.4 Vegetative Stabilization (Agricultural Lands)

- Disturbed areas on land used for agricultural purposes that are restored to their pre-construction agricultural use are not subject to vegetative stabilization standards.

16.5 Non-Vegetative Stabilization

If using non-vegetative controls to stabilize exposed portions of your site, or if you are using such controls to temporarily protect areas that are being vegetatively stabilized, you must provide effective

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	33 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

non-vegetative cover to stabilize any such exposed portions of the site. Examples of non-vegetative stabilization techniques include, but are not limited to, rip-rap, gabions, and geotextiles.

17.0 Clean-up and Restoration Standards

The following steps shall be taken once construction has been completed at each location along the ROW or within the project site. The following are minimum guidelines for clean-up and stabilization standards. Please refer to permit conditions for project-specific related standards. Refer to the EFI for applicable permit requirements and to determine if the site needs to be reviewed and approved by the permitting authorities prior to removal of erosion controls.

17.1 Removal of Sedimentation and Erosion Controls

After all work has been satisfactorily completed and vegetation has been re-established to a minimum of 75% cover, and upon approval by the National Grid Environmental Scientist, all non-biodegradable materials (e.g., siltation fencing, straw bale strings, stakes, straw wattle mesh casing, etc.) shall be disposed of properly off-site.

Dependent on permit requirements, sedimentation and erosion controls may not be allowed to be removed until after inspection and approval by one or more permitting authority. In most cases, removed straw bales may be used to mulch disturbed areas. Remaining straw bales that do not block the flow of water may be left in place unless they are required to be removed pursuant to permit conditions. Straw bales that block the flow of water shall be removed.

Prior to project construction being completed, the project team will develop post-construction inspection intervals to ensure timely removal of temporary BMPs. BMPs will be removed when the area is stabilized, which typically occurs when the area has either naturally stabilized (75% cover), or seed and mulch that was installed has achieved 75% cover.


17.2 In-Situ Restoration

Unless otherwise specified in permits or prescribed by the National Grid Environmental Scientist or the Project Environmental Consultant, all disturbed areas, including stream banks, wetlands and access routes, shall be restored following the completion of work. When the work is completed and construction mats have been removed, the National Grid Environmental Scientist or Project Environmental Consultant shall conduct an inspection. Wetlands shall be inspected for build up of sand or other materials that may have fallen through construction mats. Care shall be taken to inspect wetland crossings carefully after construction mat removal to ensure any materials are properly removed and disposed of off-site.

Restoration of Soil Compaction. If rutting or soil compaction following construction mat removal is observed, the area shall be returned to pre-existing conditions, and comparable to the surrounding area, by light hand raking or by back-blading with machinery. Restoration shall be overseen by the Project Environmental Consultant or National Grid Environmental Scientist. Deep ruts (>12") shall be filled in using available, loose soil from the work area.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	34 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Seeding and Mulching. If adequate root and seed stock are absent and have been stripped from the area, graded sites shall be promptly stabilized by applying an approved seed mix and mulching with straw to reduce erosion and visual impact. Seeding and mulching shall be completed as soon as possible following completion of work at the site. For some wetland areas, natural re-vegetation may be more appropriate than seeding disturbed sites. Wetland areas where adequate root and seed stock are absent will be seeded using an approved wetland native seed mix. For some wetland areas, natural re-vegetation may be more appropriate than seeding disturbed sites. Refer to BMPs in **Appendix 4** for seed mix tables and mulch ratio tables.

If needed, the import of quality topsoil onto the ROW will be required. Topsoil should be tested, and approved by the Project Environmental Consultant or National Grid Environmental Scientist to determine its suitability for site conditions. Fertilizers will be approved on a case-by-case basis.

For upland areas, the disturbed vegetation and soil shall be restored and stabilized⁴ by regrading the area to pre-existing conditions, if needed, seeding (if adequate root and seed stock are absent) and mulching the exposed soil, and removing strings and stakes from straw bales and using broken up straw bales for the mulch. Siltation fencing, strings and stakes shall be removed for disposal as ordinary waste. Refer to BMPs in **Appendix 4** for seed mix tables and mulch ratio tables.

For sites with excess boulders, additional boulders could be used at proposed and existing gate locations to use on either side of the gates as a deterrent for unauthorized vehicle access or be placed along the edges of work pads where steep slopes are present for safety purposes. The final placement of boulders should be reviewed prior to installation with Real Estate and the National Grid Environmental Scientist or Project Environmental Consultant.


Unless otherwise specified in Project-specific permit conditions, the National Grid Environmental Scientist or Project Environmental Consultant shall develop an inspection frequency to monitor restored areas for stabilization, germination and successful revegetation.

17.3 Invasive Species

All equipment shall be certified clean⁵ utilizing the attached form (**Appendix 5**) or equivalent as approved by the vendor prior to mobilization to the work site. The vendor shall use the certification from provided as **Appendix 5** to document compliance with invasive species management BMPs. Clean is defined as being free of plant matter (stems, flowers, roots, etc), soil, or other deleterious materials prior to being brought to the project site. Any equipment that has been placed or used within areas containing invasive species within the project site shall be cleaned of plant matter (stems, flowers, roots, etc), soil, or other deleterious materials at the site of the invasive species prior to being moved to other areas on the project

⁴ For projects subject to the 2012 CGP, stabilization is required within 14 days, or within 7 days for sensitive areas.

⁵ The **Appendix 5** certification form (or equivalent as approved by National Grid Environmental Scientist) shall be used to document the clean certification

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	35 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

site to prevent the spread of invasive species from one area to another⁶. **Equipment shall be cleaned prior to being removed at the completion of the project: exceptions to this requirement shall be determined on a case-by-case basis.** Consult with the National Grid Environmental Scientist prior to discharging or disposing of any waste water or waste material from the cleaning of equipment.

17.4 Cleaning of Equipment

At the completion of the project, equipment shall be cleaned prior to being de-mobilized to prevent tracking of material onto roads and causing safety issues. Consult with the National Grid Environmental Scientist prior to discharging or disposing of any waste water or waste material from the cleaning of equipment.

17.5 Access Roads

Constructed gravel roads shall be left in place following project completion unless permit conditions require their removal. Refer to the specific permit conditions for these provisions. If the road is to be removed, the crushed stone and geotextile fabric shall be removed from the work site. Seeding and/or mulching of gravel roads is generally not required, unless necessary to prevent erosion. Pre-existing sandy soils within mapped rare turtle habitat shall not be seeded unless directed by the National Grid Environmental Scientist so as to not alter nesting habitat.

17.6 Stone Work Pads

Unless permit conditions or property owner's require the removal of constructed stone work pads following project completion, constructed work pads shall be left in place. Refer to the specific permit conditions for these provisions.


17.7 Construction Materials on ROWs

As soon as the structure work has been completed, all used parts and trash are to be picked up and removed from the project site. Retired poles shall be removed in accordance with National Grid Engineering Standard SP.06.01.301. In some cases, the used material from structure work may be temporarily stored at the work area by placing it out of the wetlands or other sensitive resource area until work in the adjacent areas has been completed. However, treated wood poles shall never be stored in standing water or in wetlands. If the project is cancelled, all material shall be removed from the project site. Excess material brought to the project site shall be removed upon project completion. Consult with the National Grid Environmental Scientist on whether the work site shall be restored in addition to the measures outlined above

17.8 Improved Areas

Yards, lawns, agricultural areas, and other improved areas shall be returned to a condition at least equal to that which existed at the start of the project. Off-ROW access shall never be assumed and shall be coordinated through Real Estate before being implemented. Depending on the access point, construction matting or other BMPs may be required to prevent ruts, lawn damage, or other property damage.

⁶ On ROW projects where multiple wetlands may be dominated by the same invasive species, cleaning may not be required for movement along the ROW. Check with the National Grid Environmental Scientist for guidance.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	36 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Restoration following the completion of work and any use of improved areas shall be conducted in accordance with the measures outlined above.

17.9 Property Damage

All damage to property occurring as a result of a project shall be immediately repaired or replaced. In some locations, it may be desirable to document pre-existing damage prior to work commencing in that area in order to demonstrate afterwards that the damage did not result from the project. Work crews, the Project Environmental Consultant or the National Grid Environmental Scientist shall document repairs that were performed in response to damage from unauthorized vehicle use.

17.10 Overall Work Site

Upon satisfactory completion of work, the construction personnel shall remove all work-related trailers, buildings, rubbish, waste soil, temporary structures, and unused materials belonging to them or used under their direction during construction, or waste materials from previous construction and maintenance operations. All areas shall be left clean, without any litter or equipment (wire, pole butts, anchors, insulators, cross-arms, cardboard, coffee cups, water bottles, etc.) and restored to a stable condition and as near as possible to its original condition, where feasible. Debris and spent equipment shall be returned to the operating facility or contractor staging area for disposal or recycling (cardboard) as appropriate in accordance with EI-111.

17.11 Material Storage/Staging and Parking Areas

Upon completion of all work, all material storage yards, staging areas, and parking areas shall be completely cleared of all waste and debris. Unless otherwise directed or unless other arrangements have been made with an off ROW or off-property owner, material storage yards and staging areas shall be returned to the condition that existed prior to the installation of the material storage yard or staging area. Regardless of arrangements made with a landowner, all areas shall be restored to their pre-construction condition or better. Also any temporary structures erected by the construction personnel, including fences, shall be removed by the construction personnel and the area restored as near as possible to its original condition, including seeding and mulching as needed.

18.0 Notification of Emergency Work


Because it is sometimes difficult to identify wetlands and other sensitive environmental areas, the National Grid Environmental Scientist shall be notified within 24 hours or by the next working day whenever emergency off-road repair work takes place. Although the routine maintenance and emergency repair work is generally allowed, due to site conditions or the scope of the project, notification to the regulating agencies may be required.

19.0 Appendices

APPENDIX 1:	Glossary
APPENDIX 2:	Acronyms

Approved for use per EP – 10, Document Control.


PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	37 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

APPENDIX 3:	Storm Water, Wetlands & Priority Habitat Environmental Compliance Site Inspection / Monitoring Report Form
APPENDIX 4:	BMP Drawings and Guidelines
APPENDIX 5:	Certification Sheet for Invasive Species Control
APPENDIX 6:	Snow Disposal Guidelines

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	38 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Appendix 1 – Glossary

Access Road – An existing, periodically maintained road often consisting of gravel and/or exposed soils or vegetated with grasses but devoid of woody vegetation, that is visible on aerial photography and shown on ROW T-sheets. May include newly permitted permanent roads (i.e., roads to be constructed in accordance with a project-specific permit).

Access Route - A pathway previously used or proposed to be used by crews for access along the ROW. Routes may be shown on ROW T-sheets or previous project access plans but are not improved as maintained gravel/exposed soil roads. Access routes may be mown and can consist of trails utilized by recreational vehicles.

Action Logs – Project-specific log used to document action items required for permit compliance. The log identifies timeframes for completion and responsible parties. The log is typically updated by the Project Environmental Consultant or the National Grid Environment Scientist and circulated to the project team on a weekly, or more frequent, basis.

Bank – The transitional slope immediately adjacent to the edge of a surface water body, the upper limit of which is usually defined by a break in slope, or, for a wetland, where a line delineated in accordance with applicable state and federal regulations that indicates a change from wetland to upland.

BMP – Best Management Practice. Individual engineered constructions or operating procedures intended to minimize and mitigate soil disturbance, erosion, sedimentation, turbid discharges, and/or impacts to sensitive receptors.

Clean - Free of plant matter (stems, flowers, roots, etc), soil, or other deleterious materials prior to being brought to the project site.

Clean Gravel – Gravel is a type of coarse-grained soil that consists of small stones and other mineral particles. Clean Gravel shall meet the requirements in accordance with National Grid Standard Construction Specification for Electric Stations (Engineering Standard SP.08.00.001) Clean Gravel will not have fine materials that could lead to a turbid discharge.


Clean Stone (Crushed Stone) – Clean Stone (Crushed Stone) shall meet the requirements in accordance with National Grid Standard Construction Specification for Electric Stations (Engineering Standard SP.08.00.001). Clean Stone will not have fine materials that could lead to a turbid discharge.

Clearing – The cutting of trees and large bushes by hand and/or mechanical means.

Compost Socks – Tubular devices comprised of non-degradable, photodegradable, or biodegradable mesh tubing containing organic compost matrix. Compost socks are effective for intercepting site runoff, trapping

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	39 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

sediment, and treating for soluble pollutants by filtering stormwater runoff. . Compost socks are a useful sedimentation control device along construction site perimeters, as check dams in drainage channels, as a slope interruption practice on long and/or steep slopes, and around drain or street curb inlets.

Construction Mats - Construction, swamp, and timber mats (“construction mats”) are generic terms used to describe structures that distribute equipment weight to minimize disturbance to wetland soil and vegetation while facilitating passage and providing work platforms for workers and equipment. They are comprised of sheets or mats made from a variety of materials in various sizes.

Corduroy Road – Corduroy roads are cut trees and/or saplings with the crowns and branches removed, and the trunks lined up next to one another.

Dewatering Basin – An established containment area for saturated materials and pumped discharges. This measure is used for the purpose of de-watering soils prior to transport off site or for use in another location on site, and for allowing suspended sediment to settle out of pumped discharges.

Detention/Retention Basin – A detention/retention basin is designed for the purpose of detaining or retaining water. A dewatering basin is a form of detention basin

Dewatering – Use of a system of pumps, pipes and temporary holding dams to drain or divert waterways or wetlands, or lower the groundwater table before and during excavation activities.

Drainage Ditch or Swale – A clearly noticeable channel that is typically dry, except after precipitation events. Intermittent and perennial streams and rivers are not included in this definition.

Dredge – To dig, excavate, or otherwise disturb the contour or integrity of sediments in the bank or bed of a wetland, a surface water body, or other area within the regulating bodies’ jurisdiction.

Dredge Spoils – Material removed as the result of dredging.


Embankment – A protective bank constructed of mounded earth or fill materials located between a roadway (or rail bed) and a seasonal stream or other wetland.

Environmental Field Issue – Document that contains copies of all project-specific environmental permits and summarizes all environmental permit conditions. The EFI is prepared by the Project Environmental Consultant or the National Grid Environment Scientist and copies are provided to the Project Manager, Construction Supervisor(s), and other team members as appropriate.

Environmental Monitoring Records – Examples of checklists and/or monitoring reports suggested for use by the Company Environmental Engineer to document conformance of the project with this Environmental Guidance and or project specific permit/license conditions.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	40 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

Environmental Scientist – Formerly Environmental Engineer. The National Grid Environmental Department representative for the project or the territory where the work is located. For a map of Environmental Department staff territories, refer to the Environmental page of the National Grid infonet.

Environmentally Sensitive Areas – Examples of environmentally sensitive areas that may be found on National Grid properties are rivers, streams, ponds, lakes, wetlands, bogs, swamps, salt marshes, rare species habitat, wellhead protection areas, cultural sites, parks, preserves, schools and as otherwise defined by Federal, State or local regulations. Refer to EG-301.

Erosion Controls – The utilization of methods to prevent soil detachment and minimize displacement or washing down slopes by rainfall or run-off. Common practices include, but are not limited to:

- (a) Temporary and Permanent Seeding.
- (b) Mulching, Soil Binders, Tackifiers.
- (c) Erosion Control Blankets.
- (d) Hydraulic Erosion Control.

Excavate/Excavation – To dig, remove, or form a cavity or a hole in an area within the department's jurisdiction.

Fill (n.) – Any rock, soil, gravel, sand or other such material that has been deposited or caused to be deposited by human activity.

Fill (v.) – To place or deposit materials in or on a wetland, surface water body, bank or otherwise in or on an area within the jurisdiction of the department.

Flats – Relatively level landforms composed of unconsolidated mineral and organic sediments usually mud or sand, that are alternately flooded and exposed by the tides and that usually are continuous with the shore.

Frozen Condition – Field conditions when the upper portion of the ground surface freezes or when areas of standing water freeze solid such that vehicle passage over these areas is supported without any resulting soil disturbance. The frozen conditions must have been affected by severe cold (maximum daily temperatures less than 32 degrees F) for a continuous 2-week period.


GAA – Rhode Island groundwater classification, groundwater resources that are known, or presumed to be suitable for drinking water use without treatment, and are located in one of the three areas described below.

a) The state's major stratified drift aquifers that are capable of serving as a significant source for a public water supply ("groundwater reservoirs") and the critical portion of their recharge area as delineated by DEM;

b) The wellhead protection area for each public water system community water supply well. Community water supply wells are those that serve resident populations and have at least 15 service

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	41 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

connections or serve at least 25 individuals, e. g. municipal wells and wells serving nursing homes, condominiums, mobile home parks, etc.; and

c) Groundwater dependent areas that are physically isolated from reasonable alternative water supplies and where existing groundwater warrants the highest level of protection. At present only Block Island has been designated as meeting this criterion.

GA – Rhode Island groundwater classification, groundwater resources that are known, or presumed to be suitable for drinking water use without treatment. However, groundwater classified by GA does not fall within any of the three priority areas described under the GAA classification.

Grade/Grading – The movement of soil and fill material to change the elevation of the land. The term refers to the combined actions of excavating and filling to change elevation or shape.

Grubbing – The removal of stumps/roots by mechanical means during site preparation activities.

Immediately - As soon as practicable, but no later than the end of the next work day, following the day when the earth-disturbing activities have temporarily or permanently ceased.

In-kind Replacement - Replacement using the same material, functional inverts, diameter and length as the existing item. In-kind replacement includes the substitution of a structure with a similar structure in approximately the same location as is practicable, and is approximately the same in design. The design may be altered to meet applicable utility standards, and may include alternate materials designed to prolong the life of that service.

Intermittent Stream – A stream that flows for sufficient time to develop and maintain a defined channel, but which might not flow during dry portions of the year.


In the Dry – Work done either during periods of low water or behind temporary diversions, such as Earth Dike / Drainage Swale and Lined Ditches designed and installed in accordance with best management practices.

Limit of Work/Disturbance – The approved project limits within regulated areas. All project related activities in regulated areas must be conducted within the approved limit of work/disturbance. The limit of work/disturbance shall be depicted on the approved permit site plans and in the EFI plans. Where it is warranted National Grid may require that these limits be identified in the field by flagging, construction fencing, and/or perimeter erosion controls.

Long-Term Restoration Logs - Project-specific log used to document restoration required following the completion of construction or as areas of the project have been completed (i.e., segments of ROW for a multi-mile project). The log is typically updated by the Project Environmental Consultant or the National Grid Environment Scientist and circulated to the project team on a weekly basis.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	42 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Low Flow Conditions – Low water flow that generally occurs during the summer, as a result of decreased precipitation and the removal of water by increased evaporation and evapotranspiration by vegetation. Work done under low-flow conditions minimizes the potential for environmental damage. The USACE defines the calendar dates for low flow conditions in its New England state-specific Programmatic General Permits.

Low Ground Pressure – Equipment that meets the USACE GP state-specific defined Pounds per Square Inch (PSI) ground pressure when loaded. Use of LGP equipment **requires approval** from the National Grid Environmental Scientist.

Marsh – A wetland:

- a) That is distinguished by the absence of trees and shrubs;
- b) Dominated by soft-stemmed herbaceous plants such as grasses, reeds, and sedges; and
- c) Where the water table is at or above the surface throughout the year, but can fluctuate seasonally.

Methods – Are the construction practices and procedures that take place through choosing the proper equipment, trucks and labor to execute the earth moving activities based on the existing conditions and implementing creative and sensitive scheduling for the daily activities.

NHESP - Natural Heritage Endangered Species Program; a department within the Massachusetts Division of Fisheries and Wildlife that is responsible for protecting the 176 species of vertebrate and invertebrate animals and 259 species of native plants that are officially listed as Endangered, Threatened or of Special Concern in Massachusetts.

Perennial – A stream that contains water at all times except during extreme drought.

Permanently Ceased – Is applicable to earth disturbance activities when clearing and excavation within any area of the Project that will not include permanent structures has been completed.


Person-in-Charge – A National Grid Project Engineer, Manager, Supervisor, Field Construction Coordinator or equivalent Contractor personnel assigned to oversee and coordinate work activities.

Processed Gravel – Processed Gravel shall meet the requirements in accordance with National Grid Standard Construction Specification for Electric Stations (Engineering Standard SP.08.00.001). Processed Gravel will not have fine materials that could lead to a turbid discharge. Gravel consisting of inert material that is hard, durable stone and is free from loam and clay, surface coatings and deleterious materials.

Regulating Body – Federal, State, or local authority that has jurisdiction over resource areas that may be impacted by company operations

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	43 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Regulated Wetland Area – Those areas that are subject to federal, state or local wetland regulation, including certain buffer or adjacent areas.

Repair – The restoring of an existing legal structure by partial replacement of work, or broken, or unsound parts (Env-Wt 101.73).

Replacement – The substitution of a new structure for an existing legal structure with no change in size, dimensions, location, configuration, construction, or which conforms in all material aspects to the original structure

Right-of-Way – A corridor of land where National Grid has legal rights (either fee ownership, lease or easement) to construct, operate, and maintain an electric power line and/or natural gas pipeline and may include work on customer owned properties.

River – A watercourse that is larger than a perennial stream and flows all year long.

Routine Utility Rights-of-Way Maintenance Activity – Includes but is not limited to vegetation management and repair or replacement of existing utility structures.

Sedimentation Controls – Silt fences, straw bales, compost socks/berms and other barrier devices strategically placed to intercept and treat sediment-laden site runoff.

Sensitive Water - Includes any sediment or nutrient impaired water or a water that is identified by the state, tribe or EPA as Tier 2, 2.5 or Tier 3 for antidegradation purposes.

Siltation Curtain – An impervious barrier erected to prevent silt and sand and/or fines from being washed into a wetland, surface water body or other area of concern.


Surface Water Body or Surface Waters – Those portions of waters which have standing or flowing water at or on the surface of the ground.

Spill Prevention, Control and Countermeasure Plans – Required for site operations that involve the storage of 1,320 gallons or greater of fuel and oils, both in storage containers and stored in equipment. Response actions to spills and releases are specified in these plans.

Stormwater Pollution Prevention Plan – A site-specific, written document that, among other things: (1) identifies potential sources of stormwater pollution at a construction site; (2) describes stormwater control measures to reduce or eliminate pollutants in stormwater discharge from a construction site; and (3) identifies procedures the operator will implement to comply with the terms and conditions of EPA NPDES Construction General Permit (CGP). SWPPPs must be prepared, maintained on-site, and amended as necessary in order to obtain NPDES permit coverage for specific construction site stormwater discharges under the EPA NPDES CGP.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	44 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

Temporarily Ceased - Is applicable when there are earth disturbance activities such as clearing, grading, and/or excavation that are not complete, but will be idle in one area for a period of up to 14 or more calendar days, and which will resume in the future. The 14 calendar day timeframe begins as soon as you know that construction work on a portion of the Project will be left incomplete and idle. In circumstances where there are unanticipated delays and you do not know at first how long the work stoppage will continue, the requirement to immediately initiate stabilization is triggered as soon as you know with reasonable certainty that work will be stopped for 14 or more additional calendar days.

Tidal Wetlands – A wetland whose vegetation, hydrology or soils are influenced by periodic inundation or tidal waters.

Topsoil – The uppermost part of the soil, ordinarily moved in tillage, or its equivalent in uncultivated soils and ranging in depth from 2 to 10 inches.

Turbidity – The condition in which solid particles suspended in water make the water cloudy or even opaque in extreme cases.

United States Geological Survey Topographic Map – A map that uses contour lines to represent the three-dimensional features of a landscape on a two-dimensional surface. These maps use a line and symbol representation of natural and artificially created features in an area.

Wetland – An area that is inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal conditions does support, a prevalence of vegetation (more than 50 percent) typically adapted for life in saturated soil conditions (hydric soils). Wetlands include but are not limited to swamps, marshes, bogs, and similar areas.


Work Site – An area where work is performed.

Worker – Company employee, contractor, consultant working on site.

Zone II - Massachusetts - That area of an aquifer which contributes water to a well under the most severe pumping and recharge conditions that can be realistically anticipated (180 days of pumping at safe yield, with no recharge from precipitation). It is bounded by the groundwater divides which result from pumping the well and by the contact of the aquifer with less permeable materials such as till or bedrock. In some cases, streams or lakes may act as recharge boundaries. In all cases, Zone IIs shall extend up gradient to its point of intersection with prevailing hydrogeologic boundaries (a groundwater flow divide, a contact with till or bedrock, or a recharge boundary).

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	45 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Appendix 2 – Acronyms

ASTM	American Society for Testing and Materials
BMP	Best Management Practices
EFI	Environmental Field Issue
EG	Environmental Guidance
EPA	Environmental Protection Agency
GA/GAA	Rhode Island Groundwater Classifications – see glossary
LGP	Low Ground Pressure
MA	Massachusetts
MA DEP	Massachusetts Department of Environmental Protection
MassDOT	Massachusetts Department of Transportation
NE	New England
NH	New Hampshire
NH DES	New Hampshire Department of Environmental Services
NHESP	Natural Heritage Endangered Species Program
NPDES	National Pollutant Discharge Elimination System
OHM	Oil and/or Hazardous Materials
PSI	Pounds per square inch
RI	Rhode Island
RI DEM	Rhode Island Department of Environmental Management
RI CRMC	Rhode Island Coastal Resources Management Council
RI SESC	Rhode Island soil erosion and sediment control
ROW	Right-of-Way
RTE	Rare, Threatened or Endangered
SPCC	Spill Prevention, Control and Countermeasure
SWPPP	Storm Water Pollution Prevention Plan
TOY	Time-of-Year
USACE	United States Army Corps of Engineers
USGS	United States Geological Survey
VT	Vermont

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	46 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

VT DEC Vermont Department of Environmental Conservation

Zone II Massachusetts Groundwater Protection district – see glossary

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	47 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Appendix 3

See EG303NE_Appendix3_Reporting Form published separately

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	48 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	


Appendix 4 – BMPs

See EG303NE_Form1 for a list of BMPS

See EG303NE_Form2 for BMP details

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE
	Rev. No.:	15
	Page No.:	49 of 50
	Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

APPENDIX 5
CERTIFICATION FORM FOR INVASIVE SPECIES CONTROL

Certain permit conditions, therefore a Condition of Contracts for the Prime Contractor, any Subcontractors, and any equipment or mat vendors for **National Grid Projects** shall be required to Certify their equipment⁷ {each piece of equipment used on site} as 'clean'⁸.

_____ (name of firm) hereby Certifies that
 _____ (make, model, and/or type)
 _____ (equipment ID tag or #) meets the following

1. before entry on to the job site, has been sufficiently cleaned to remove all accumulated mud, debris, plant fragments, and detritus that could harbor seeds, roots, or plant fragments of so-called invasive plant species; and
2. that the above piece of equipment has neither been off-loaded nor operated in the interval between cleaning and delivery to the jobsite.
3. that equipment deployed in areas of invasive species (as identified in project plans) shall be cleaned prior to redeployment.

_____ (signed) _____ (dated)
 _____ (printed name) _____ (title)
 _____ (Firm)

The signed original of this form {one for each piece of equipment (or lot⁹ of mats)} is to be given to the NG Construction Supervisor assigned to the project.


⁷ Equipment may include, but is not limited to bulldozers, excavators, backhoes, bucket trucks (tracked or wheeled), pulling equipment, concrete trucks, compressors, drilling equipment, and mats (composite, wood, or other materials).

⁸ With regard to invasive species, the definition of clean means free of accumulated mud, debris, plant fragments, and detritus that could harbor seeds, roots, or plant fragments of so-called invasive plant species.

⁹ Lot of mats is the number of mats that may be transported by one forwarder/truck at a time.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	15
		Page No.:	50 of 50
		Date:	08/06/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Appendix 6 – Snow Disposal Guidelines

See EG303NE_App6 published separately

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance	Doc No.:	EG-303NE_App4_Form1
	Rev. No.:	6
	Page No.:	1 of 2
	Date:	04/13/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection


	BMP #	Measure
Sediment & Erosion Controls	SEC-1	Weed free bale barrier
	SEC-2	Sediment control fence
	SEC-3	Silt fence / weed free barrier
	SEC-4	Silt Soxx
	SEC-5	Straw Wattle
	SEC-6	Erosion Control Blanket - Ditch
	SEC-7	Erosion Control Blanket - Slope
	SEC-8	Hydroseeding with Tackifier (slope stabilization)
	SEC-9	Mulch materials, rates and uses (from NY)
	SEC-10	Seeding options - Upland Seed Mixes
	SEC-11	Seeding options - Wetland Seed Mix
	SEC-12	Distribution Pole Erosion Control

Crossing Measures	CM-1	Prefabricated mats
	CM-2	Construction mat bridge
	CM-3	Construction mat layout (with transition)
	CM-4	Construction mat layout (with transition & BMPs)
	CM-5	Construction mat - Air Bridge
	CM-6	Corduroy road
	CM-7	Rock Ford
	CM-8	Temporary construction entrance / exit
	CM-9	Temporary construction culvert
	CM-10	Access way stabilization
	CM-11	Construction signage
	CM-12	Construction Mat Anchoring

Advanced Applications	AA-1	Reinforced silt fence
	AA-2	Sediment filter
	AA-3	Stone check dams
	AA-4	Straw / haybale check dam
	AA-5	Waterbar
	AA-6	Sandbag check dam
	AA-7	Earth dike
	AA-8	Drainage swale and lined ditch
	AA-9	Sedimentation basin
	AA-10	Dewatering basin - Small scale
	AA-11	Dewatering basin - Large scale
	AA-12	Dirtbag
	AA-13	Concrete waste sump

Approved for use per EP 10, Document Control

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE

 National Grid Environmental Guidance	Doc No.:	EG-303NE_App4_Form1
	Rev. No.:	6
	Page No.:	2 of 2
	Date:	04/13/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection

	AA-14	Outpak concrete washout
Advanced Applications	AA-15	Barrier fence (construction fence)
	AA-16	ROW gates / fences
	AA-17	Bollard
	AA-18	Dust control
	AA-19	Catch Basin Inlet Protection
	AA-20	Silt Sack
	AA-21	Turbidity Curtain
	AA-22	Siltsoxx Amphibian & Reptile Crossing #1
	AA-23	Siltsoxx Amphibian & Reptile Crossing #2
	AA-24	Siltsoxx Amphibian & Reptile Crossing #3
	AA-25	Cultural Avoidance

Approved for use per EP 10, Document Control

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. THE GROUND SHALL BE PREPARED TO PROVIDE COMPLETE CONTACT WITH THE BALES.

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-1

WEED FREE BALE BARRIER

SUBJECT




Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

PROFILESECTIONPLAN**BMP PICTURE**

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-2
SEDIMENT CONTROL FENCE

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. BALES SHALL BE PLACED IN A ROW WITH THE ENDS TIGHTLY ABUTTING THE ADJACENT BALES.
2. BALES SHALL BE SECURELY ANCHORED IN PLACE BY TWO (2) 1"x1"x36" HARDWOOD STAKES DRIVEN THROUGH THE BALES. THE FIRST STAKE IN EACH BALE SHALL BE ANGLED TOWARD PREVIOUSLY LAID BALE TO FORCE BALES TOGETHER.
3. INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
4. BALES SHALL BE REMOVED AND REPLACED WHEN THEY BECOME FILLED WITH SEDIMENT AND BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.
5. BALES SHALL BE REMOVED WHEN THE EMBANKMENTS STABILIZE.
6. BALES TO BE TWINE BOUND.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


SEC-3
SILT FENCE /
WEED FREE BARRIER

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

**NOTES**

1. PRODUCT TO BE FILTREXX SILT SOXX OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
3. FILTER MEDIA FILL TO MEET APPLICATION REQUIREMENTS.
4. MESH CONTAINMENT MATERIAL SHOULD BE KNITTED PHOTODEGRADABLE OR BIODEGRADABLE MATERIAL, WITH OPENING SIZES BETWEEN 1/8" – 3/8".
5. COMPOST MEDIA SHOULD HAVE PARTICLE SIZE WHERE 99% < 2", 50% > 1/2".
6. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.

BMP PICTURE

* PICTURE AND DETAIL PROVIDED BY FILTREXX LAND IMPROVEMENT SYSTEMS
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-4
SILT SOXX *

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. PRODUCT TO BE TENSAR NORTH AMERICAN GREEN STRAW WATTLE OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. TYPICAL WATTLE SPACING BASED ON SLOPE GRADIENT. COORDINATE SPACING AND LOCATION WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.
3. MINIMUM 12" DIAMETER WATTLES SHOULD BE USED FOR HIGHLY DISTURBED AREAS (I.E., HEAVILY USED ACCESS ROAD WITH ADJACENT WETLAND) AND MINIMUM 9-10" WATTLES SHOULD BE USED FOR LESS DISTURBED SOILS.

INSTALLATION NOTES:

1. BEGIN AT THE LOCATION WHERE THE WATTLE IS TO BE INSTALLED BY EXCAVATING A 2-3" DEEP X 9" WIDE TRENCH ALONG THE CONTOUR OF THE SLOPE. EXCAVATED SOIL SHOULD BE PLACED UPSLOPE FROM THE ANCHOR TRENCH.
2. PLACE THE WATTLE IN THE TRENCH SO THAT IT CONTOURS TO THE SOIL SURFACE. COMPACT SOIL FROM THE EXCAVATED TRENCH AGAINST THE WATTLE ON THE UPHILL SIDE. ADJACENT WATTLES SHOULD TIGHTLY ABUT.
3. SECURE THE WATTLE WITH 18-24" HARDWOOD STAKES EVERY 3-4' AND WITH A STAKE ON EACH END. STAKES SHOULD BE DRIVEN THROUGH THE MIDDLE OF THE WATTLE LEAVING AT LEAST 2-3" OF STAKE EXTENDING ABOVE THE WATTLE. STAKES SHOULD BE DRIVEN PERPENDICULAR TO THE SLOPE FACE.

* DETAIL AND PICTURE PROVIDED BY TENSAR NORTH AMERICAN GREEN
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-5
STRAW WATTLE * (1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE

STRAW WATTLE – SHALLOW SLOPE ($\leq 4:1$)
(ALTERNATE STAKING)

ALTERNATE STAKING INSTALLATION NOTES:

1. ON SHALLOW SLOPES ($\leq 4:1$), STRAW WATTLE MAY BE SECURED WITH 18–24" HARDWOOD STAKES DRIVEN AGAINST THE SIDES OF THE WATTLE INSTEAD OF THROUGH. STAKES SHALL ALTERNATE SIDES, AND BE SPACED 3–4' MAX.
2. TWINE SHALL BE TIED FROM STAKE TO STAKE, CRISS-CROSSING THE STRAW WATTLE. TIE TWINE TO STAKES BELOW THE HEIGHT OF THE WATTLE.

SUBJECT

Access, Maintenance and Construction
Best Management Practices



Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

CIRCLED NUMBERS CORRESPOND TO
INSTALLATION NOTES ON PAGE 2 OF
2 FOR THIS EROSION CONTROL
BLANKET - DITCH BMP DETAIL (TYP.)

**CRITICAL POINTS**

- A. OVERLAPS AND SEAMS
- B. PROJECTED WATER LINE
- C. CHANNEL BOTTOM/SIDE SLOPE VERTICES

NOTES:

1. PRODUCT TO BE NORTH AMERICAN GREEN EROSION CONTROL BLANKET OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. HORIZONTAL STAPLE SPACING SHOULD BE ALTERED IF NECESSARY TO ALLOW STAPLES TO SECURE THE CRITICAL POINTS ALONG THE CHANNEL SURFACE.
3. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY ANCHOR THE ROLLED EROSION CONTROL PRODUCTS (RECP's).

* PICTURE AND DETAIL PROVIDED BY TENSAR NORTH AMERICAN GREEN
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-6
EROSION CONTROL BLANKET -
DITCH * (1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL**INSTALLATION NOTES:**

1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE RECP's IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH WITH APPROXIMATELY 12" (30 CM) OF RECP's EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP's WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECP's BACK OVER SEED AND COMPACTED SOIL. SECURE RECP's OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) ACROSS THE WIDTH OF THE RECP's.
3. ROLL CENTER RECP's IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. RECP's WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP's MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
4. PLACE CONSECUTIVE RECP's END OVER END (SHINGLE STYLE) WITH A 4" – 6" (10 CM –15 CM) OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER TO SECURE RECP's.
5. FULL LENGTH EDGE OF RECP's AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
6. ADJACENT RECP's MUST BE OVERLAPPED APPROXIMATELY 2" – 5" (5 CM –12.5 CM) (DEPENDING ON RECP's TYPE) AND STAPLED.
7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9 M – 12 M) INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.
8. THE TERMINAL END OF THE RECP's MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

BMP PICTURE

* PICTURE AND DETAIL PROVIDED BY TENSAR NORTH AMERICAN GREEN
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-6
EROSION CONTROL BLANKET -
DITCH * (2 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices


Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

CIRCLED NUMBERS CORRESPOND
TO INSTALLATION NOTES FOR THIS
EROSION CONTROL BLANKET –
SLOPE BMP DETAIL (TYP.)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. PRODUCT TO BE NORTH AMERICAN GREEN EROSION CONTROL BLANKET OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLES OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY SECURE THE RECPS's.

INSTALLATION NOTES:

1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECPS's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECPS IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH WITH APPROXIMATELY 12" (30 CM) OF RECPS EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECPS WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECPS BACK OVER SEED AND COMPACTED SOIL. SECURE RECPS OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) APART ACROSS THE WIDTH OF THE RECPS's.
3. ROLL THE RECPS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECPS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECPS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
4. THE EDGES OF PARALLEL RECPS MUST BE STAPLED WITH APPROXIMATELY 2" – 5" (5 CM – 12.5 CM) OVERLAP DEPENDING ON RECPS TYPE.
5. CONSECUTIVE RECPS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5 CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30 CM) APART ACROSS ENTIRE RECPS WIDTH.

* PICTURE AND DETAIL PROVIDED BY TENSAR NORTH AMERICAN GREEN
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-7
EROSION CONTROL BLANKET -
SLOPE * (1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE

File: Erosion_Blanket_Slope.dwg

* PICTURE AND DETAIL PROVIDED BY TENSAR NORTH AMERICAN GREEN
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-7
EROSION CONTROL BLANKET -
SLOPE * (2 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURENOTES:

1. COORDINATE MIXTURE TYPE AND APPLICATION AREAS WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST PRIOR TO CONSTRUCTION.
2. A MINIMUM OF 1500 LBS. PER ACRE OF A PAPER/CORN FIBER OR EQUIVALENT WITH NATURAL TACKIFIERS WILL BE USED ON SLOPES LESS THAN 3:1.
3. A BFM (BONDED FIBER MATRIX) WILL BE USED ON SLOPES GREATER THAN 2:1.
4. A FGM (FLEXIBLE GROWTH MATRIX) OR ESM (EXTREME SLOPE MATRIX) WILL BE USED ON SLOPES GREATER THAN 1:1.
5. REFER TO BMP #10 FOR SEED MIXTURE OPTIONS.

* PICTURE PROVIDED BY TENSAR NORTH AMERICAN GREEN

* TACKIFIER INFORMATION PROVIDED BY FILTREXX LAND IMPROVEMENT SYSTEMS AND TENSAR NORTH AMERICAN GREEN

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-8

HYDROSEEDING WITH TACKIFIER
(SLOPE STABILIZATION) *

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP**Definition**

Applying coarse plant residue or chips, or other suitable materials, to cover the soil surface.

Purpose

The primary purpose is to provide initial erosion control while a seeding or shrub planting is establishing. Mulch will conserve moisture and modify the surface soil temperature and reduce fluctuation of both. Mulch will prevent soil surface crusting and aid in weed control. Mulch is also used alone for temporary stabilization in non-growing months.

Conditions Where Practice Applies

On soils subject to erosion and on new seedlings and shrub plantings. Mulch is useful on soils with low infiltration rates by retarding runoff.

Criteria

Site preparation prior to mulching requires the installation of necessary erosion control or water management practices and drainage systems.

Slope, grade and smooth the site to fit needs of selected mulch products.

Remove all undesirable stones and other debris to meet the needs of the anticipated land use and maintenance required.

Apply mulch after soil amendments and planting is accomplished or simultaneously if hydroseeding is used.

Select appropriate mulch material and application rate or material needs. Determine local availability.

Select appropriate mulch anchoring material.

NOTE: The best combination for grass/legume establishment is straw (cereal grain) mulch applied at 2 ton/acre (90 lbs./1000sq.ft.) and anchored with wood fiber mulch (hydromulch) at 500 – 750 lbs./acre (11 – 17 lbs./1000 sq. ft.). The wood fiber mulch must be applied through a hydroseeder immediately after mulching.

**NOTE:**

1. PICTURE DEPICTS STRAW MULCH APPLICATION (FROM MULCH SPREADER) ON STEEP SLOPE WITH AN IMPROVED DRAINAGE SWALE.
2. COORDINATE MULCH MATERIALS AND RATES WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

* BMP INFORMATION FROM "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL (AUGUST, 2005)." INFORMATION OBTAINED VIA WEBSITE: <http://www.dec.ny.gov/chemical/29086.html>
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-9

MULCH MATERIALS, RATES AND
USES (FROM NY) *

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

UPLAND ROW RESTORATION MIX – GENERAL

Species Composition Options:

- Andropogon gerardii; Niagra Big Bluestem
- Schizachyrium scoparium; Little Bluestem
- Elymus Canadensis; Canada Wild Rye
- Elymus virginicus; Virginia Wildrye
- Lolium multiflorum; Annual Ryegrass
- Sorghastrum nutans; Indiangrass
- Chamaecrista fasciculata; Partridge Pea
- Desmodium canadense; Showy Tick Trefoil
- Heliopsis helianthoides; Ox-Eye Sunflower
- Panicum virgatum; Switchgrass
- Rudbeckia hirta; Black Eyed Susan
- Poa palustris; Fowl Bluegrass
- Agrostis perennans; Upland Bentgrass
- Agrostis alba; Redtop
- Festuca rubra; Red Fescue
- Lotus corniculatus; Birds-Foot Trefoil
- Chrysanthemum leucanthem; Ox-Eye Daisy
- Aster novae-angliae; New England Aster

Example Seed Mixes:

1. Native Upland wildlife forage and Cover Meadow Mix – Ernst Conservation Seeds (ERNMX-123)
2. Eastern Ecotype Native Grass Mix– Ernst Conservation Seeds (ERNMX-177)
3. New England Native Warm Season Grass Mix – New England Wetland Plants, Inc.
4. New England Logging Road Mix – New England Wetland Plants, Inc.
5. Northeast Upland Wildflower/Restoration Erosion Mix – Southern Tier Consulting (STCMX-2)

UPLAND ROW RESTORATION MIX – DRY/ROCKY SITES

Species Composition Options:

- Festuca rubra; Red Fescue
- Schizachyrium scoparium; Little Bluestem
- Elymus Canadensis; Canada Wild Rye
- Bouteloua gracilis; Blue Grama
- Lolium multiflorum; Annual Ryegrass
- Lolium perenne; Perennial Ryegrass
- Agrostis scabra; Rough Bentgrass
- Agrostis perennans; Upland Bentgrass
- Sorghastrum nutans; Indiangrass

Example Seed Mixes:

1. New England Erosion Control/ Restoration Mix for Dry Sites – New England Wetland Plants, Inc.
2. Ernst Conservation Seeds and similar companies can create a custom seed mix matching the composition above (with site specific additions if necessary).

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

WETLAND ROW RESTORATION MIXSpecies Composition Options:

- Agrostis stolonifera; Creeping Bentgrass
- Poa trivialis; Rough Bluegrass
- Alopecurus arundinaceus; Creeping Meadow Foxtail
- Lolium multiflorum; Annual Ryegrass
- Festuca rubra; Creeping Red Fescue
- Elymus virginicus; Virginia Wildrye
- Schizachyrium scoparium; Little Bluestem
- Andropogon gerardii; Niagra Big Bluestem
- Carex vulpinoidea; Fox sedge
- Panicum virgatum; Switchgrass
- Agrostis scabra; Rough Bentgrass
- Aster novae-angliae; New England Aster
- Eupatorium perfoliatum; Boneset
- Euthamia graminifolia; Grass Leaved Goldenrod
- Scirpus atrovirens; Green Bulrush
- Verbena hastata; Blue Vervain
- Juncus effusus; Soft Rush
- Scirpus cyperinus; Wool Grass
- Panicum clandestinum; Deertongue

Example Seed Mixes

1. New England Erosion Control/Restoration Mix for Detention Basins and Moist Sites – New England Wetland Plants, Inc.
2. Northeast Wetland Grass Seed Mix – Southern Tier Consulting (STCMX-7)
3. Ernst Conservation Seeds and similar companies can create a custom seed mix matching the composition above (with site specific additions if necessary).

GERNERAL NOTES:

1. Seed mixes described herein are intended to cover a variety of typical new england landscapes. However, site specific seed mixes will need to be evaluated in coastal or mountainous regions.
2. Seed mixes described herein are intended for general ROW restoration. Site specific wetland seed mixes may be required by local, state and/or federal regulators for certain impacts to wetlands.
3. All seed mixes are to be approved by National Grid Environmental Scientist prior to construction and must conform with all project permits.
4. Seedbed preparation and maintenance as well as temporary erosion and sediment controls are crucial to the establishment of newly seeded areas. Coordinate with National Grid Environmental Scientist on seed bed preparation and maintenance as well as temporary erosion and sediment controls prior to construction.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-11

SEEDING OPTIONS -
WETLAND SEED MIX

SUBJECT



Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

SECTION A-APLANNOTES

1. PRODUCT TO BE STRAW WATTLE OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST (SEE SEC-5 BMP DETAIL).
2. STRAW BALE BARRIER PER SEC-1 BMP DETAIL TO BE AN AVAILABLE ALTERNATE DEPENDING ON SITE CONDITIONS AT THE DIRECTION OF NATIONAL GRID ENVIRONMENTAL SCIENTIST (SEE FIGURE 2).
3. MINIMUM CLEARANCE BETWEEN POLE AND EROSION CONTROL TO BE DETERMINED BY CONDITIONS OF POLE INSTALLATION/REPLACEMENT WORK AND ASSOCIATED DISTURBANCE.

BMP PICTURE

FIGURE 1: TYP. STRAW WATTLE APPLICATION



FIGURE 2: ALT. STRAW BALE APPLICATION

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SEC-12
DISTRIBUTION POLE
SEDIMENT CONTROL

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE

SCALE: NONE

**NOTES:**

1. PRODUCT TO BE ALTURNAMATS' PREFABRICATED MATS OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. PRODUCT AVAILABLE IN 4X8' UNITS.
3. IF MATS ARE INSTALLED IN A WETLAND AREA, INSTALL EROSION CONTROLS TO CONTAIN MATERIAL UTILIZED IN THE MAT TRANSITIONS.

* PICTURE PROVIDED BY ALTURNAMATS

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


CM-1
PREFABRICATED MATS *

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL**NOTES:**

1. IF MATS ARE INSTALLED IN A WETLAND AREA, INSTALL EROSION CONTROLS TO CONTAIN MATERIAL UTILIZED IN THE MAT TRANSITIONS.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-2
CONSTRUCTION MAT BRIDGE
(1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE - SINGLE SPAN

SCALE: NONE

**NOTES:**

1. WHERE STREAM WIDTH ALLOWS, INSTALL CONSTRUCTION MATS TO SPAN THE WATERCOURSE IN ITS ENTIRETY WITHOUT STRINGER PLACEMENT IN THE WATER OR ANY RESTRICTION OF STREAM FLOW.
2. INSTALLATION OF THE CONSTRUCTION MAT BRIDGE SHALL NOT DAMAGE THE STREAM BED AND BANKS. WHERE POSSIBLE, FOOTERS SHALL BE PLACED PARALLEL TO THE TOP OF THE STREAM BANKS, WITH ACCESS MATTING PLACED ACROSS THE TOP OF THE STRINGERS DISTRIBUTING THE WEIGHT OF THE CONSTRUCTION EQUIPMENT.
3. AT STREAM CROSSINGS THAT CANNOT BE SPANNED BY A SINGLE SECTION OF CONSTRUCTION MATTING, AND WHERE PERMITS ALLOW, STRINGERS SHALL BE PLACED ATOP THE STREAM BED PARALLEL TO THE FLOW OF WATER.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-2

CONSTRUCTION MAT BRIDGE

(2 OF 2)

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. TO BE INSTALLED IF NECESSARY TO PREVENT RUTTING, TO ACCESS STRUCTURES.
2. THIS DETAIL SHOWS TYPICAL DIMENSIONS. SOME CONTRACTOR'S CONSTRUCTION MATS ARE DIMENSIONALLY DIFFERENT FROM WHAT IS SHOWN HERE.
3. DEPENDENT ON SITE CONDITIONS, MULTIPLE LAYERS OF CONSTRUCTION MATS MAY BE INSTALLED.

BMP PICTURE

CM-3

CONSTRUCTION MAT LAYOUT
(WITH TRANSITION)

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. ADD FILTER FABRIC AS NEEDED UNDER STONE TRANSITION RAMPS.
2. ALL MEASUREMENTS AND LOCATIONS ARE APPROXIMATE.

BMP PICTURE**CM-4**

CONSTRUCTION MAT LAYOUT
(WITH TRANSITION AND BMPs)

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. THE DETAIL SHOWN IS CONCEPTUAL. CONSTRUCTION MATS AND CROSS TIMBERS SHALL BE SIZED AND SELECTED BASED ON SPAN WIDTH, CROSSING EQUIPMENT AND FIELD CONDITIONS.
2. THE NUMBER OF CONSTRUCTION MATS MAY VARY DEPENDING ON THE CLEARANCE HEIGHT.
3. EQUIPMENT AND PERSONNEL LOAD SHALL BE DISTRIBUTED ON ALL TIMBERS.
4. EACH EQUIPMENT OPERATOR AND USER OF THE FIELD BRIDGE SHALL BE FAMILIAR WITH THE DESIGN AND THE MAXIMUM EQUIPMENT AND PERSONNEL LOADS.
5. THIS DETAIL MAY NOT BE APPLICABLE IN ALL FIELD CONDITIONS.
6. INSTALL EROSION CONTROLS ADJACENT TO THE CULVERT ENDS TO PROTECT THE WATERWAY FROM ROADWAY DEBRIS.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES


PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-5

CONSTRUCTION MAT - AIR BRIDGE

SUBJECTAccess, Maintenance and Construction
Best Management Practices**Reference**EP No. 3 - Natural Resource
Protection (Chapter 6)**BMP DETAIL**

SCALE: NONE



RANDOM LENGTH AND DIAMETER LOGS PLACED ACROSS AN ACCESS ROAD

NOTE:

1. A SIMILAR BRUSH MAT INSTALLATION CONSISTING OF SMALLER DIAMETER STEMS AND LOGS CAN BE USED.
2. CORDUROY ROADS SHALL ONLY BE USED IN EMERGENCIES OR AFTER APPROVAL FROM THE PROJECT ENVIRONMENTAL CONSULTANT OR NATIONAL GRID ENVIRONMENTAL SCIENTIST.

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.**CM-6**
CORDUROY ROAD

SUBJECT



Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**BMP PICTURE**

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-7
ROCK FORD

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. STONE SIZE – USE 2" STONE (MINIMUM) TO 6" STONE (MAXIMUM)
2. LENGTH – GREATER THAN OR EQUAL TO 50 FEET
3. THICKNESS – 4"
4. WIDTH – FIFTEEN (15) FOOT TYP., BUT NOT LESS THAN FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
5. SURFACE WATER – ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS ENTRANCE. IF PIPING IS IMPRACTICAL, MOUNTABLE BERM SHALL BE PERMITTED.
6. MAINTENANCE – THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
7. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED.
8. THE CLEAN STONE SHOULD BE INSTALLED OVER A GEOTEXTILE FABRIC. GEOTEXTILE FABRIC MAY BE OMITTED FOR PERMANENT CONSTRUCTION ENTRANCES/EXITS ON A CASE-BY-CASE BASIS WITH THE APPROVAL OF THE NATIONAL GRID ENVIRONMENTAL SCIENTIST.
9. FOLLOWING CONSTRUCTION, THE CONSTRUCTION ENTRANCE/EXIT SHALL BE REMOVED AND THE AREA GRADED, SEEDED, AND MULCHED AS NEEDED. ENTRANCE/EXITS MAY REMAIN DEPENDING UPON FUTURE ACCESS NEEDS AND/OR PROJECT-SPECIFIC APPROVALS BUT REQUIRES APPROVALS FROM THE NATIONAL GRID ENVIRONMENTAL SCIENTIST AND PROPERTY LEGAL.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-8
TEMPORARY CONSTRUCTION
ENTRANCE/ EXIT

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference


EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL


SCALE: NONE



CROSS SECTION



SECTION 'A-A'
(SAME BOTH ENDS)



SECTION 'B-B'

CM-9
TEMPORARY CONSTRUCTION
CULVERT (1 OF 2)

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL**NOTES:**

SCALE: NONE

1. CULVERT DESIGN AND LAYOUT SHALL BE COORDINATED WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST (NGES).
2. CROWN ROADWAY 1/2 INCH PER FOOT.
3. LAY THE CULVERT STRAIGHT AND AS NEARLY AS POSSIBLE ALONG THE EXISTING STREAM BED AND WITH THE INVERTS AT OR SLIGHTLY BELOW BED ELEVATION.
4. CORRUGATED METAL PIPE IS TO BE GALVANIZED STEEL, OR ALUMINIZED STEEL (TYPE 2), WITH BOLTED CONNECTORS.
5. DIAMETERS SHALL BE AS PER THE PROJECT DRAWINGS AND THE SPECIFICATION. THE PIPE GAGE SHALL BE AS FOLLOWS:

DIAMETER (INCHES)	GAGE
12" – 15"	.004"
18" – 24"	.079"
30" – 36"	.109"

6. INSTALLATION OF CULVERTS LARGER THAN 36 INCH DIAMETER SHALL REQUIRE SPECIAL ENGINEERING DESIGN.
7. SELECT SUBGRADE SHALL BE A GRANULAR MATERIAL AS DESCRIBED IN NYSDOT SPECIFICATION ITEM 203–2.02C, OR AS APPROVED BY A NGES.
8. STONE RIPRAP SHALL BE AS DESCRIBED IN NYSDOT SPECIFICATION ITEM 203–2.02D, WITH 8 INCH MAXIMUM SIZE, OR AS APPROVED BY A NGES. EXCEPT WHERE PROTECTED BY STONE, ALL EMBANKMENT SLOPES ARE TO BE STABILIZED, MULCHED AND SEEDED AS PER PROJECT SPECIFICATIONS.
9. OUTLET SHOULD BE CONFIGURED NOT TO CREATE HYDRAULIC JUMP OR PLUNGE POOL.
10. INSTALL EROSION CONTROLS ADJACENT TO THE CULVERT ENDS TO PROTECT THE WATERWAY FROM ROADWAY DEBRIS.

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-9

**TEMPORARY CONSTRUCTION
CULVERT (2 OF 2)**

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURENOTE:

1. PICTURE SHOWS VIEW OF ACCESS WAY STABILIZATION ADJACENT TO A WETLAND.
2. COORDINATE STABILIZATION DESIGN AND PRODUCT WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE

NO ACCESS – WETLAND/STREAM CROSSING MATS REQUIRED



NO ACCESS – A.) PROJECT LIMITS E.G. ROW LIMITS
B.) HISTORICAL/CULTURAL
C.) ENVIRONMENTALLY SENSITIVE E.G. THREATENED & ENDANGERED
D.) OTHER



APPROVED ACCESS

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-11
CONSTRUCTION SIGNAGE

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL 1


SCALE: NONE

TYPICAL PLAN VIEWNOTES:

1. EXAMPLES OF ANCHORING ONLY. MATTING CONTRACTOR SHALL PROPOSE THE METHOD OF ANCHORING BASED ON FIELD CONDITIONS.
2. ANCHORING METHOD TO BE APPROVED BY THE NATIONAL GRID ENVIRONMENTAL SCIENTIST AND TRANSMISSION LINE CONSTRUCTION SUPERVISOR.

BMP DETAIL 2NOTES:

1. TYPICAL HELICAL ANCHOR AND CABLE CONFIGURATION FOR MAT CONTAINMENT IN FLOODPLAINS/LAND SUBJECT TO FLOODING.
2. TYPICAL POINTS OF ATTACHMENT HEAVY STAPLES, EYE BOLTS OR OTHER SUITABLE HARDWARE TO SECURE ATTACHMENT OF MAT TO LINEAR CABLE. IF CHAIN POCKETS ARE PRESENT IN THE MATS CABLE OR ROPE CAN BE LOOPED THROUGH RODS.

**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-12


EXAMPLE OF CONSTRUCTION MAT
ANCHORING (1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE 1BMP PICTURE 2

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

CM-12

EXAMPLE OF CONSTRUCTION MAT
ANCHORING (2 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

WIRE BACKED SILT FENCE

**MUTUAL INDUSTRIES WIRE BACKED SILT FENCE**

PART # 1776-14-24

36" X 100'

36" MISF 1776 FABRIC

24" 14GA WIRE MESH

OPENING OF MESH 2" X 4"

FABRIC HOG RINGED EVERY 12"-18" ALONG THE TOP OF THE FENCE

ROLL WEIGHT 40 LBS

32 ROLLS PER PALLET

NOTES:

1. PRODUCT TO BE MUTUAL INDUSTRIES' WIRE BACKED SILT FENCE OR APPROVED EQUAL BY NATIONAL ENVIRONMENTAL SCIENTIST.
2. COORDINATE INSTALLATION METHOD AND LOCATION WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

* PICTURE AND DETAIL PROVIDED BY MUTUAL INDUSTRIES

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-1

REINFORCED SILT FENCE *

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURENOTE:

1. PICTURE SHOWS SEDIMENT FILTER WITHIN A WETLAND.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-2
SEDIMENT FILTER

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**STONE CHECK DAM****NOTES:**

1. USE CHECK DAMS TO SLOW WATER FLOWS AND AS SMALL SEDIMENT TRAPS IN DITCHES ALONG ACCESS ROADS.
2. CLEAN SEDIMENT AND REPLACE DAMS AS NECESSARY.
3. THE CENTER OF THE CHECK DAM MUST BE AT LEAST 6" LOWER THAN THE OUTER EDGES.
4. COORDINATE SPACING WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.
5. MAX. SPACING: TOE OF THE UPSTREAM DAM IS SAME ELEVATION AS TOP OF DOWNSTREAM DAM.
6. STONE SHALL BE FREE OF FINE PARTICLES TO PREVENT TURBID DISCHARGES.

BMP PICTURE

NOTE: A SMALLER STONE SIZE IS SHOWN IN THIS PICTURE.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-3
STONE CHECK DAMS

SUBJECT

Access, Maintenance and Construction
Best Management Practices



Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

3' HARDWOOD
STAKES OR
Ø5/8" REBAR

PLAN VIEWSECTION VIEWNOTES:

1. USE CHECK DAMS TO SLOW WATER FLOWS AND AS SMALL SEDIMENT TRAPS IN DITCHES ALONG ACCESS ROADS.
2. CLEAN SEDIMENT AND REPLACE DAMS AS NECESSARY.
3. COORDINATE SPACING WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-4


STRAW / HAYBALE CHECK DAM

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

**NOTE:**

1. LINE WITH 2"-6" STONE UNDERLAIN BY GEOTEXTILE FILTER FABRIC, KEYED INTO ROAD SURFACE AT LEAST 10 FEET EACH SIDE OF WATERBAR.
2. COORDINATE SPACING WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-5
WATERBAR

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**SANDBAG
CHECK DAM****NOTES:**

1. USE CHECK DAMS TO SLOW WATER FLOWS AND AS SMALL SEDIMENT TRAPS IN DITCHES ALONG ACCESS ROADS.
2. CLEAN SEDIMENT AND REPLACE DAMS AS NECESSARY.
3. COORDINATE SPACING WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

BMP PICTURE**NOTE:**

1. PICTURE DOES NOT DEPICT "TAMP IN BACKFILL"

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-6
SANDBAG CHECK DAM

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURENOTE:

1. EXACT SIZE, LOCATION AND DESIGN IS DEPENDANT ON SITE CONDITIONS, AND LOCAL AND STATE REGULATIONS. COORDINATE THIS BMP WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST PRIOR TO CONSTRUCTION.


APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-7
EARTH DIKE

SUBJECTAccess, Maintenance and Construction
Best Management Practices**Reference**EP No. 3 - Natural Resource
Protection (Chapter 6)**BMP DETAIL**

SCALE: NONE

**NOTES:**

1. WIDTH AND DEPTH OF SWALE, AND EROSION CONTROL BLANKET TYPE TO BE COORDINATED WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. REFER TO DETAILS SEC-10 AND SEC-11 FOR SEED MIXTURE OPTIONS.


BMP PICTURE**AA-8****DRAINAGE SWALE AND
LINED DITCH****APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL**TYPICAL PROFILE****NOTES**

1. SIZE, SHAPE AND PROFILE OF SEDIMENT WILL VARY ACCORDING TO ANTICIPATED FLOW VOLUME AND SURROUNDING TERRAIN AND SHALL BE COORDIANATED WITH THE NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. THE BASIN SHALL BE CUT BELOW THE GROUNDLINE. FILL SHALL NOT BE USED TO HOLD WATER UNLESS ROLLED AND COMPACTED.
3. OUTLET AREA IS TO REMAIN FREE OF EXCAVATION SPOILS.
4. OUTLET CREST ELEVATION SHALL BE LOWER THAN INLET ELEVATION AND AT LEAST 1'-0" BELOW THE TOP OF THE BASIN. ARMOUR SLOPES >8% IN OUTLET AREA WITH STONE OF APPROPRIATE SIZE TO PREVENT SCOUR.
5. ARMOUR SLOPES >8% IN OUTLET AREA WITH STONE OF APPROPRIATE SIZE TO PREVENT SCOUR.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

**AA-9
SEDIMENTATION BASIN**

SUBJECT

Access, Maintenance and Construction
Best Management Practices



Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

FIELD VARIABLE

**NOTES:**

1. NUMBER OF BALES MAY VARY DEPENDING ON SITE CONDITIONS,
2. THE BASIN TO BE SIZED TO PREVENT DISCHARGE WATER FROM OVERTOPPING BASIN.
3. KEEP AS FAR FROM WETLANDS AS PRACTICAL.
4. CLEAN AND REMOVE AS SOON AS DEWATERING IS COMPLETE.

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-10
DEWATERING BASIN
(SMALL SCALE)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURENOTE:


1. EXACT SIZE, LOCATION AND DESIGN IS DEPENDANT ON SITE CONDITIONS, AND LOCAL AND STATE REGULATIONS. COORDINATE THIS BMP WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST PRIOR TO CONSTRUCTION.

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

**NOTE:**

ONCE PUMPING COMMENCES, THE DIRT BAG SHALL BE MONITORED FREQUENTLY TO ASSURE THAT THE CONNECTIONS ARE SECURELY FASTENED AND THE RATE OF WATER DELIVERY TO THE STRUCTURE IS LOW ENOUGH TO PREVENT UNFILTERED WATER FROM FLOWING FROM THE HOSE CONNECTIONS OR BAG.

BMP PICTURE

* PICTURE AND DETAIL PROVIDED BY ACF ENVIRONMENTAL

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


AA-12
DIRTBAG *

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL**NOTES:**

1. NUMBER OF BALES MAY VARY DEPENDING ON SITE CONDITIONS. COORDINATE SIZE AND LOCATION OF CONCRETE WASTE SUMP WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. KEEP AS FAR FROM DRAINAGE CHANNELS AND WETLAND AREAS AS PRACTICAL.
3. SUMPS TO BE CLEANED AND WASTE CONCRETE REMOVED AND PROPERLY DISPOSED OF UPON COMPLETION OF WORK.
4. SEE ADDITIONAL NOTES ON DETAIL AA-14.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.


AA-13
CONCRETE WASTE SUMP

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL**NOTES:****CROSS SECTION**

1. PRODUCT TO BE OUTPAK PVC CONCRETE WASHOUT OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. THE CONCRETE WASHOUT AREA SHALL BE INSTALLED PRIOR TO ANY CONCRETE PLACEMENT.
3. SIGNS SHALL BE PLACED AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CONCRETE WASHOUT.
4. THE CONCRETE WASHOUT AREA WILL BE REPLACED AS NECESSARY TO MAINTAIN CAPACITY FOR WASTE CONCRETE AND OTHER LIQUID WASTE.
5. WASHOUT RESIDUE SHALL BE REMOVED FROM THE SITE AND DISPENSED OF AT AN APPROVED WASTE SITE.
6. DO NOT MIX EXCESS AMOUNTS OF FRESH CONCRETE OR CEMENT ON-SITE.
7. DO NOT WASH OUT CONCRETE TRUCKS INTO STORM DRAINS, OPEN DITCHES, STREETS, OR STREAMS.
8. AVOID DUMPING EXCESS CONCRETE IN NON-DESIGNATED DUMPING AREAS.
9. LOCATE WASHOUT AREA AT LEAST 50' FROM STORM DRAIN, OPEN DITCHES, OR WATERBODIES. COORDINATE LOCATION WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.
10. WASH OUT WASTES INTO THE OUTPAK WASHOUT WHERE THE CONCRETE CAN SET, BE BROKEN UP, AND THEN DISPOSED OF PROPERLY.
11. A SECURE, NON-COLLAPSING, NON-WATER COLLECTING COVER MUST BE PLACED OVER CONCRETE WASHOUT PRIOR TO PREDICTED WET WEATHER TO PREVENT ACCUMULATION AND OVERFLOW OF PRECIPITATION.

BMP PICTURE

* PICTURE AND DETAIL PROVIDED BY OUTPAK WASHOUT
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-14
OUTPAK CONCRETE WASHOUT *

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE



SECTION A-A

BMP PICTURE



AA-15

**BARRIER FENCE
(CONSTRUCTION FENCE)**

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)



4" ϕ DES PIPE
GATE WELDMENT

BMP DETAIL

SCALE: NONE

DETAIL 2

DETAIL 1

DETAIL 1

SIMILAR DETAIL AT TOP

ROUND PIECE CUT FROM
1/4" PLATE AND WELDED

4" ϕ DES PIPE
1 1/4" ϕ ROD
(SLOTTED)

6" ϕ STD PIPE
WELDED TO 3/8"
PLATE

7" X 3/8" X 10" PLATE
WITH HOLE CUT TO FIT
6" ϕ PIPE & WELDED

6" ϕ PIPE
POST

DOUBLE LOCK
INSERT PLATE

DETAIL 2NOTES:

1. ALL GATE STEEL PIPES SHALL BE IN ACCORDANCE WITH ASTM A-501, PLATES SHALL BE ASTM A-36.
2. ALL STEEL PIPES SHALL BE PRIMED WITH ZINC-CHROMATE PRIMER AND FINISHED WITH AN APPROVED OSHA "SAFETY YELLOW" TOP COAT COMPATIBLE WITH THE PRIMER AND FOR EXTERIOR EXPOSURE.
3. REFLECTORS SHALL BE SPACED AT 3 FEET ALONG THE LENGTH OF THE CROSSBAR AND BRACE
4. BACKFILL AT POSTS TO BE COMPACTED.

BMP PICTURE

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-16
ROW GATE / FENCE

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference


EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. ALL CONCRETE TO BE 2500 P.S.I. MINIMUM.
2. COORDINATE LOCATIONS WITH NATIONAL GRID ENVIRONMENTAL SCIENTIST.

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-17
BOLLARD

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP

**Definition**

The control of dust resulting from land-disturbing activities.

Purpose

To prevent surface and air movement of dust from disturbed soil surfaces that may cause off-site damage, health hazards, and traffic safety problems.

Conditions Where Practice Applies

On construction roads, access points, and other disturbed areas subject to surface dust movement and dust blowing where off-site damage may occur if dust is not controlled.

Design Criteria

Construction operations should be scheduled to minimize the amount of area disturbed at one time. Buffer areas of vegetation should be left where practical. Temporary or permanent stabilization measures shall be installed. No specific design criteria is given; see construction specifications below for common methods of dust control.

Water quality must be considered when materials are selected for dust control. Where there is a potential for the material to wash off to a stream, ingredient information must be provided to the local permitting authority.

Construction Specifications

A. Non-driving Areas – These areas use products and materials applied or placed on soil surfaces to prevent airborne migration of soil particles.

* BMP INFORMATION FROM "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL (AUGUST, 2005)." INFORMATION OBTAINED VIA WEBSITE: <http://www.dec.ny.gov/chemical/29086.html>
APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES
PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

Vegetative Cover – For disturbed areas not subject to traffic, vegetation provides the most practical method of dust control (see Section 3).

Mulch (including gravel mulch) – Mulch offers a fast effective means of controlling dust. This can also include rolled erosion control blankets.

Spray adhesives – These are products generally composed of polymers in a liquid or solid form that are mixed with water to form an emulsion that is sprayed on the soil surface with typical hydroseeding equipment. The mixing ratios and application rates will be in accordance with the manufacturer's recommendations for the specific soils on the site. In no case should the application of these adhesives be made on wet soils or if there is a probability of precipitation within 48 hours of its proposed use. Material Safety Data Sheets will be provided to all applicators and others working with the material.

B. Driving Areas – These areas utilize water, polymer emulsions, and barriers to prevent dust movement from the traffic surface into the air.

Sprinkling – The site may be sprayed with water until the surface is wet. This is especially effective on haul roads and access routes.

Polymer Additives – These polymers are mixed with water and applied to the driving surface by a water truck with a gravity feed drip bar, spray bar or automated distributor truck. The mixing ratios and application rates will be in accordance with the manufacturer's recommendations. Incorporation of the emulsion into the soil will be done to the appropriate depth based on expected traffic. Compaction after incorporation will be by vibratory roller to a minimum of 95%. The prepared surface shall be moist and no application of the polymer will be made if there is a probability of precipitation within 48 hours of its proposed use. Material Safety Data Sheets will be provided to all applicators working with the material.

Barriers – Woven geotextiles can be placed on the driving surface to effectively reduce dust throw and particle migration on haul roads. Stone can also be used for construction roads for effective dust control.

Windbreak – A silt fence or similar barrier can control air currents at intervals equal to ten times the barrier height. Preserve existing wind barrier vegetation as much as practical.

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. SURROUND STREET DRAINAGE STRUCTURE INLET WITH HAY BALES PRIOR TO CONSTRUCTION AND MAINTAIN UNTIL CONSTRUCTION IS COMPLETED. ACCUMULATED SEDIMENTS SHALL BE REMOVED.
2. HAYBALES PLACED ON PAVEMENT SHALL HAVE BURLAP PLACED BETWEEN PAVEMENT AND HAYBALE

BMP PICTURE**APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES**

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-19

CATCH BASIN INLET PROTECTION

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**BMP PICTURE**

* DETAIL PROVIDED BY ACF ENVIRONMENTAL

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-20
SILT SACK *

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**BMP PICTURE**

* DETAIL PROVIDED BY BROCKTON EQUIPMENT / SPILLDAM INC.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

AA-21
TURBIDITY CURTAIN *

SUBJECT




Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

PLANSECTIONPROFILENOTES

1. PRODUCT TO BE FILTREXX SILT SOXX OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
3. FILTER MEDIA FILL TO MEET APPLICATION REQUIREMENTS.
4. NON-MONOFILAMENT CONTAINMENT MATERIAL SHOULD BE KNITTED PHOTODEGRADABLE OR BIODEGRADABLE MATERIAL, WITH OPENING SIZES BETWEEN 1/8" - 1/4".
5. COMPOST MEDIA SHOULD HAVE PARTICLE SIZE WHERE 99% < 2", 50% > 1/2".
6. COMPOST MATERIAL TO BE DISPOSED OF ON-SITE, OR IN ACCORDANCE WITH ENVIRONMENTAL PERMITS AS APPROVED BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
7. WOOD MULCH RAMP IS OPTIONAL DEPENDING ON SUBSTRATE/SITE CONDITIONS, AND TO BE APPROVED BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

BMP # AA-22
SILT SOXX AMPHIBIAN & REPTILE
CROSSING #1 (1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE

SALAMANDER AND SNAKE CROSSING #1

ALTERNATE WOOD MULCH RAMP SILTSOXX NOTES:

1. SILTSOXX, BY FILTREX INTERNATIONAL, OR APPROVED EQUAL PRODUCT SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURER'S GUIDELINES.
2. BMP SHOULD ONLY BE UTILIZED IN AREAS WHERE RARE SALAMANDER AND SNAKE HABITAT OCCURS, OR AT THE DIRECTION OF THE NATIONAL GRID ENVIRONMENTAL SCIENTIST.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

BMP # AA-22
SILTSOXX AMPHIBIAN & REPTILE
CROSSING #1 (2 OF 2)

SUBJECT




Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

PLANSECTIONPROFILENOTES

1. PRODUCT TO BE FILTREXX SILT SOXX OR APPROVED EQUAL BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
2. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
3. FILTER MEDIA FILL TO MEET APPLICATION REQUIREMENTS.
4. NON-MONOFILAMENT CONTAINMENT MATERIAL SHOULD BE KNITTED PHOTODEGRADABLE OR BIODEGRADABLE MATERIAL, WITH OPENING SIZES BETWEEN 1/8" - 1/4".
5. COMPOST MEDIA SHOULD HAVE PARTICLE SIZE WHERE 99% < 2", 50% > 1/2".
6. COMPOST MATERIAL TO BE DISPOSED OF ON-SITE, OR IN ACCORDANCE WITH ENVIRONMENTAL PERMITS AS APPROVED BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
7. WOOD MULCH RAMP IS OPTIONAL DEPENDING ON SUBSTRATE/SITE CONDITIONS, AND TO BE APPROVED BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
8. GAPS TO BE SPACED EVERY 50 FT, IF POSSIBLE GIVEN WETLAND PERMIT CONDITIONS.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

BMP # AA-23
SILT SOXX AMPHIBIAN & REPTILE
CROSSING #2 (1 OF 2)

SUBJECT

Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURE

SILTSOXX AMPHIBIAN & REPTILE CROSSING #2

ALTERNATE WOOD MULCH RAMP SILTSOXX NOTES:

1. SILTSOXX, BY FILTREX INTERNATIONAL, OR APPROVED EQUAL PRODUCT SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURER'S GUIDELINES.
2. BMP SHOULD ONLY BE UTILIZED IN AREAS WHERE RARE SALAMANDER AND SNAKE HABITAT OCCURS OR AT THE DIRECTION OF THE NATIONAL GRID ENVIRONMENTAL SCIENTIST.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

BMP # AA-23
SILTSOXX AMPHIBIAN & REPTILE
CROSSING #2 (2 OF 2)

SUBJECT




Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES**

1. IN AREAS WHERE SLOPES OR RUN-OFF VOLUME PROHIBIT USE OF SILT SOXX, CROSSINGS CAN BE PROVIDED THROUGH TRENCHED SILT FENCE.
2. INSTALL SILT FENCE TO SPECIFICATIONS IN EG303 APPENDIX 7 "SEC-2 SEDIMENT CONTROL FENCE."
3. WOOD MULCH RAMP IS OPTIONAL DEPENDING ON SUBSTRATE/SITE CONDITIONS, AND TO BE APPROVED BY NATIONAL GRID ENVIRONMENTAL SCIENTIST.
4. GAPS TO BE SPACED EVERY 50 FT, IF POSSIBLE GIVEN WETLAND PERMIT CONDITIONS.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

BMP # AA-24
SILT FENCE AMPHIBIAN & REPTILE
CROSSING #3

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP DETAIL

SCALE: NONE

**NOTES:**

1. ARCHAEOLOGICAL SITE BOUNDARIES, AS DEFINED BY INTENSIVE ARCHAEOLOGICAL SURVEY AND SITE AVOIDANCE AND PROTECTION PLANS, WILL BE DEMARCATED BY STAKING BY THE PROJECT ARCHAEOLOGIST.
2. GEOTEXTILE AND STONE MAY REMAIN IN PLACE FOLLOWING CONSTRUCTION IF PERMANENT PROTECTION IS NECESSARY AND DEPENDENT ON EASEMENT RIGHTS.
3. WHERE APPROVED BY THE PROJECT-SPECIFIC SAPP, CONSTRUCTION MATTING MAY BE ADDED OVER, OR IN PLACE OF, THE FABRIC AND STONE.
4. INSTALLATION AND REMOVAL OF FABRIC AND STONE, EROSION CONTROLS, AND/OR CONSTRUCTION MATTING WILL BE MONITORED BY THE PROJECT ARCHAEOLOGIST AT EACH LOCATION(S).
5. INSTALLATION OF THESE MEASURES WILL BE CONDUCTED WITH LOW-GROUND PRESSURE VEHICLES WHERE FEASIBLE.
6. WHERE REQUIRED BY THE PROJECT-SPECIFIC SAPP, TEMPORARY, HIGH VISIBILITY PROTECTIVE FENCING (E.G., SNOW FENCE OR PLASTIC FENCE) WILL BE ERECTED ALONG THE SITE BOUNDARIES OUTSIDE OF THE WORKSPACE WITHIN THE ROW IN ORDER TO PREVENT VEHICLES FROM TRAVELING THROUGH THOSE SITE AREAS DURING CONSTRUCTION. THE PROTECTIVE FENCE WILL BE POSTED WITH "NO TRESPASSING" SIGNS, SO THAT THE SITES CAN BE AVOIDED BY ALL CONSTRUCTION RELATED ACTIVITIES. THE FENCING WILL BE REMOVED UPON COMPLETION OF THE PROJECT. THE INSTALLATION AND REMOVAL OF FENCING WILL BE MONITORED BY THE PROJECT ARCHAEOLOGIST.

APPROVED BY: VICE PRESIDENT, ENVIRONMENTAL SERVICES

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED
VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

BMP # AA-25**CULTURAL AVOIDANCE (1 OF 2)**

SUBJECT


Access, Maintenance and Construction
Best Management Practices

Reference

EP No. 3 - Natural Resource
Protection (Chapter 6)

BMP PICTURES



 National Grid Environmental Guidance		Doc No.:	EG-303NE
		Rev. No.:	14
		Page No.:	48 of 49
		Date:	06/02/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

APPENDIX 5
CERTIFICATION FORM FOR INVASIVE SPECIES CONTROL

Certain permit conditions, therefore a Condition of Contracts for the Prime Contractor, any Subcontractors, and any equipment or mat vendors for **National Grid Projects** shall be required to Certify their equipment⁷ {each piece of equipment used on site} as 'clean'⁸.

_____ (*name of firm*) hereby Certifies that
 _____ (*make, model, and/or type*)
 _____ (*equipment ID tag or #*) meets the following

1. before entry on to the job site, has been sufficiently cleaned to remove all accumulated mud, debris, plant fragments, and detritus that could harbor seeds, roots, or plant fragments of so-called invasive plant species; and
2. that the above piece of equipment has neither been off-loaded nor operated in the interval between cleaning and delivery to the jobsite.
3. that equipment deployed in areas of invasive species (as identified in project plans) shall be cleaned prior to redeployment.

_____ (*signed*) _____ (*dated*)
 _____ (*printed name*) _____ (*title*)
 _____ (*Firm*)

The signed original of this form {one for each piece of equipment (or lot⁹ of mats)} is to be given to the NG Construction Supervisor assigned to the project.


⁷ Equipment may include, but is not limited to bulldozers, excavators, backhoes, bucket trucks (tracked or wheeled), pulling equipment, concrete trucks, compressors, drilling equipment, and mats (composite, wood, or other materials).

⁸ With regard to invasive species, the definition of clean means free of accumulated mud, debris, plant fragments, and detritus that could harbor seeds, roots, or plant fragments of so-called invasive plant species.

⁹ Lot of mats is the number of mats that may be transported by one forwarder/truck at a time.

Approved for use per EP – 10, Document Control.

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE.

 National Grid Environmental Guidance		Doc No.:	EG-303NE_App6
		Rev. No.:	1
		Page No.:	1 of 2
		Date:	04/13/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

APPENDIX 6

SNOW DISPOSAL GUIDELINES

Finding a place to dispose of collected snow poses a challenge. While we are all aware of the threats to public safety caused by snow, collected snow that is contaminated with road salt, sand, litter, and automotive pollutants such as oil also threatens public health and the environment.

As snow melts, road salt, sand, litter, and other pollutants are transported into surface water or through the soil where they may eventually reach the groundwater. Road salt and other pollutants can contaminate water supplies and are toxic to aquatic life at certain levels. Sand washed into water bodies can create sand bars or fill in wetlands and ponds, impacting aquatic life, causing flooding, and affecting our use of these resources.

There are several steps that should be taken to minimize the impacts of snow disposal on public health and the environment.


- **DO NOT** dump snow into any water body, including rivers, the ocean, reservoirs, ponds, or wetlands. In fact, a buffer of at least 50 feet between any snow disposal area and any the high-water mark of any surface water should be kept. A silt fence or equivalent barrier should be securely placed between the snow storage area and the high-water mark. In addition to water quality impacts and flooding, snow disposed in surface waters can cause navigational hazards when it freezes into ice blocks.
- **DO NOT** dump snow within a wellhead protection area (e.g., a Zone II), in a high or medium-yield aquifer, or within 75 feet of a private well, where road salt may contaminate water supplies. **Ask an Environmental Department representative for guidance in determining if a proposed disposal area is located within one of these sensitive areas.**
- Avoid disposing of snow on top of storm drain catch basins or in storm water drainage swales or ditches. Snow combined with sand and debris may block a storm drainage system, causing localized flooding. A high volume of sand, sediment, and litter released from melting snow also may be quickly transported through the system into surface water.
- All debris in a snow storage area should be cleared from the site and properly disposed of no later than May 15 of each year the area is used for snow storage.

Under extraordinary conditions, when all land-based snow disposal options are exhausted, disposal of snow that is not obviously contaminated with road salt, sand, and other pollutants may be allowed near (within 50 feet) or even in certain water bodies under certain conditions.

In these dire situations, **notify the Environmental Department** so that the local Conservation Commission and the appropriate MassDEP Regional Service Center (in MA), RI DEM Office of Water Resources – RIPDES

Approved for use per EP 10, Document Control

PRINTED COPIES ARE NOT DOCUMENT CONTROLLED. FOR LATEST AUTHORIZED VERSION PLEASE REFER TO THE NATIONAL GRID ENVIRONMENTAL INFONET SITE

 National Grid Environmental Guidance		Doc No.:	EG-303NE_App6
		Rev. No.:	1
		Page No.:	2 of 2
		Date:	04/13/2020
SUBJECT ROW Access, Maintenance and Construction Best Management Practices for New England		REFERENCE EP-3; Natural Resource Protection	

Program (in RI), NH Department of Environmental Services – NHDES (in NH) and VT Department of Environmental Conservation - VT DEC (in VT) can be contacted before disposing of snow in a water body.

In emergency situations and after consulting an Environmental Department representative the following guidance should be followed:

- Dispose of snow in open water with adequate flow and mixing to prevent ice dams from forming.
- Do not dispose of snow in saltmarshes, vegetated wetlands, certified vernal pools, shellfish beds, mudflats, drinking water reservoirs and their tributaries, wellhead protection areas, or other environmentally sensitive areas.
- Do not dispose of snow where trucks may cause shoreline or stream bank damage or erosion.